Copyright

by

Joseph Aloysius Campbell

1998

DISTRIBUTION STATEMENT A

Approved for public release; Distribution Unlimited

Remediation Technologies for Environmental Projects in the United States Military: Part II

by

Joseph Aloysius Campbell, B.S.M.E.

Thesis

Presented to the Faculty of the Graduate School
of the University of Texas at Austin
in Partial Fulfillment
of the Requirements
for the Degree of

Master of Science in Engineering

The University of Texas at Austin

May 1998

19980727 033

Remediation Technologies for Environmental Projects

in the United States Military: Part II

APPROVED BY

SUPERVISING COMMITTEE:

Supervisor - James T. O'Connor

John D. Borcherding

ABSTRACT

Remediation Technologies for Environmental Projects in the United States Military: Part Π

by

Joseph Aloysius Campbell, M.S.E.

The University of Texas at Austin, 1998
SUPERVISOR: James T. O'Connor

This thesis analyzes the performance of environmental restoration and compliance projects in the Department of Defense. The thesis is the second part of a two-part study examining project cost, schedule, and technical performance. The soundness of the reasons for a specific remediation technology selection are explored and tested. The research consists of data collection, statistical analysis, and formulating conclusions and recommendations. This thesis demonstrates that planning environmental restoration and compliance projects using formalized decision matrices can increase the likelihood of project success.

Table of Contents

Chapter 1.	Introduction	1
1.1	Background and Motive	1
1.2	Purpose of this Research	1
1.3	Research Scope	1
1.4	Research Hypotheses	2
1.5	Structure of this Thesis	3
Chapter 2.	Summary of Remediation Technologies for Environmental Project	s in
the United	States Military: Part I	4
2.1	Background	4
2.2	Management of Environmental Remediation Projects	5
2.3	Site Remediation Technologies	5
2.4	Remediation Technology Selection	6
Chapter 3	. Study Methodology	. 11
3.1	Development of Data Gathering Tool - Project Survey	. 12
3.2	Development of a Relational Database	. 13
3.3	Hypotheses from Part I	. 13
3.4	· · · · · · · · · · · · · · · · · · ·	. 14
3.5		15
3.6		. 15
3.7	=	
3.8	Data Collection	
3.9		22
Chapter 4.	Data Analysis	. 25
4.1	Project Performance vs. Overall Evaluation	. 25
4.2		27
4.3		. 29
4.4		31
4.5		. 32
4.6		33
4.7		35
4.8		37
4.9		39
	O Overall Evaluation vs. Reason for Technology Selection	40

4.11 Cost Performance vs. Reason for Technology Selection	42
4.12 Schedule Performance vs. Reason for Technology	
Selection	45
4.13 Scope Change vs. Reason for Technology Selection	
Sooft sammer and a second secon	
Chapter 5. Conclusions and Recommendations	46
5.1 Conclusions	46
5.2 Recommendations	
Appendices A. Research Plan from Part I.	50
B. Data Collection Tool	
C. Data Collected	
D. Chi-square Contingency Tables	91
Bibliography	100
Vita	102

List of Figures

Figure 3.1	Research Flan for Fart II	11
Figure 3.2	Data Correlations Analyzed	16
Figure 3.3	Correlations Recommended for Future Analyses	23
Figure 4.1	Overall results vs. Committee and a pr	
Figure 4.2	Cost i chomanee vs. Contaminant 2 pe	26
Figure 4.3	Schedule I chomanee is. Commission - JF	28
Figure 4.4	Overall Project Results vs. Technology Implemented	
Figure 4.5	Cost Performance vs. Technology Implemented	
Figure 4.6	Schedule Performance vs. Technology Implemented	33
Figure 4.7	Scope Change vs. Technology Implemented	35
Figure 4.8	Overall Results vs. Reason for Technology Selection	37
Figure 4.9	Cost Performance vs. Reason for Technology Selection	39
Figure 4.10	Schedule Performance vs. Reason for Technology Selection	41
Figure 4.11	Scope Change vs. Reason for Technology Selection	45

List of Tables

Table 2.1	DOD Technologies Screening Matrix	8
Table 2.2	AFCEE Remediation Matrix	. 10
Table 3.1	Chi-square Contingency Table	. 17
Table 4.1	Contaminant Present in Unsuccessful Projects	. 25
Table C-1	Project Name and Location - Data Table	. 56
Table C-2	Project Contaminant and Comments - Data Table	. 59
Table C-3	Project Reason for Technology Selection and Applicable	
	Clean-up Standards - Data Table	64
Table C-4	Project Results - Data Table	68
Table C-5	Contract Type and Cost – Data Table	. 72
Table C-6	Contract Funding and Performance – Data Table	. 76
Table C-7	Extent of Contamination – Data Table	80
Table C-8	Regulatory Goals and Remediation Technology	83
Table C-9	Site Geology	. 87
Table D-1	Chi-Square Contingency Table for Cost vs. Contaminant	. 92
Table D-2	Chi-Square Contingency Table for Schedule vs. Contaminant	93
Table D-3	Chi-Square Contingency Table for Cost vs. Technology	94
Table D-4	Chi-Square Contingency Table for Schedule vs. Technology	. 95
Table D-5	Chi-Square Contingency Table for Scope Change vs.	
	Technology	96
Table D-6	Chi-Square Contingency Table for Cost vs. Reason for Technology	logy
	Selection	. 97
Table D-7	Chi-Square Contingency Table for Schedule vs. Reason for	
	Technology Selection	. 98
Table D-8	Chi-Square Contingency Table for Scope Change vs. Reason	ı for
	Technology Selection	. 99

Chapter 1. Introduction

1.1 Background and Motive

This thesis analyzes the performance of environmental restoration and compliance projects in the Department of Defense. The thesis is the second part of a two-part study examining project cost, schedule, and technical performance on such projects. The soundness of the reasons for a specific remediation technology selection are explored and tested. The research consists of data collection, statistical analysis, and the formulation of conclusions and recommendations. This thesis demonstrates that planning environmental restoration and compliance projects using formalized decision matrices can increase the likelihood of project success.

1.2 Purpose of this Research

The primary objective of this research was to formulate a better understanding of the management of environmental restoration and compliance projects. This study provides analysis of environmental remediation technologies, their performance from a project manager's perspective, and the effectiveness of the reasons for their selection.

1.3 Research Scope

This research is part of a two-part study of project management on environmental remediation projects in the Department of Defense (DOD). Part I included the following activities:

- Research project definition
- Literature review
- Preparation of data collection instrument
- Data collection from U.S. Air Force sources
- Design and development of relational database
- Recommendations for analysis

This thesis is Part II of the study and includes:

- Data collection from U.S. Navy sources
- Application of the relational database
- Data analysis and presentation of conclusions and recommendations

1.4 Research Hypotheses

Eight hypotheses have been tested in this research. They include the following:

- 1. That project cost performance does vary with technology implemented.
- 2. That project schedule performance *does vary* with technology implemented.
- 3. That project scope performance does vary with technology implemented.
- 4. That project scope performance *does vary* with reason for technology selection.
- 5. That project cost performance does not vary with contaminant type.
- 6. That project schedule performance does not vary with contaminant type.
- 7. That project schedule performance *does not vary* with reason for technology selection.

8. That project cost performance *does not vary* with reason for technology selection.

1.5 Structure of this Thesis

Following this introductory chapter, Chapter Two is dedicated to summarizing Part I of the study, the work of Captain Scot T. Allen, USAF. Chapter Three is a detailed explanation of the research methodology. Next, a graphical presentation of the data and statistical data analysis is performed in Chapter Four. Chapter Five presents final conclusions and recommendations.

Chapter 2. Summary of Remediation Technologies for Environmental Projects in the United States Military: Part I

This thesis is the second part of a two-part study. This chapter is dedicated to summarizing Part I, the work of Captain Scot T. Allen, USAF. A complete copy of his Thesis is on record at The University of Texas at Austin.

2.1 Background

Since the enactment of the Comprehensive Environmental Response Compensation, and Liability Act (CERCLA) in 1980, when Congress established a \$1.6 billion "Superfund" for environmental remediation of past contaminated sites, it has been recognized that the costs of cleaning up polluted areas will be several orders of magnitude higher than previous estimates (LaGrega 1994). Annual spending on environmental protection and restoration in the U.S. is expected to reach \$185 billion by the year 2000 (Kenkeiemath 1996).... Cost projections for site remediation alone exceed \$1 trillion distributed over the next two decades (Blackburn 1993). (Allen 1997)

The U.S. armed forces have closed the era in American history of inattention to environmental issues and are aggressively pursuing clean up projects at Department of Defense (DOD) installations. The Department of the Navy (DON) has identified 4433 sites that require environmental investigation and possible remediation: 1382 of the sites have been remediated, 2549 sites are in the study phase, and 502 had a cleanup underway as of 30 September 1996 (DON 1996). The cost of environmental remediation is high. The Navy's Fiscal Year 1998 budget includes \$675 million for environmental studies, cleanup,

restoration, and compliance. Base realignment and closure is associated with \$361 million of that figure (USA 1998).

2.2 Management of Environmental Remediation Projects

Two aspects of environmental remediation project management that differ from conventional construction management are the technology selection decision and the way that risk is managed in the project. In the construction industry, risk is assigned through legal contracts between owners and contractors. The most common type of construction contract, lump sum (also called firm, fixed price) assigns almost all of the risk to the contractor. The cost reimbursable contract type assigns the majority of project risk to the owner. The end result of a construction contract is a tangible facility while the site of a remediation project may not look significantly different to the casual observer even after millions of dollars have been spent. The scope of an environmental remediation project may be very hard to distinctly quantify. This increased uncertainty in environmental projects makes the contract type selection more difficult. According to the Construction Industry Institute (CII), "The unusual features of contaminated site remediation projects suggest that non-traditional or innovative management and contracting strategies may be beneficial." CII research indicates that contracts, which share risk, yield better results with less cost overruns (CII 1995). (Allen 1997)

2.3 Site Remediation Technology

Captain Allen profiled the main remediation technologies currently used by the U.S. military. He discussed the pros and cons of *in situ* (in place) and *ex situ* (excavation / pumping) solutions and gave a good description of the techniques,

constraints, favorable conditions, and cost estimate ranges for the following technologies:

Soil vapor extraction Low permiability soil cap

Air sparging Passive treatment wall

Biodegradation Groundwater pump and treat

Bioventing Excavation and land disposal

Composting And several innovative technologies

Many remediation technologies have been developed to treat contaminated soil and groundwater. The Environmental Protection Agency (EPA) has supported research on these technologies through the Superfund Innovative Technology Evaluation (SITE) program and the Technical Support Project (Scalf 1992). Information on nearly 350 technologies is now available through the EPA's Hazardous Waste Clean Up Information Web site on the Vendor Information Systems for Innovative Treatment Technologies (VISITT) database. This database can be downloaded for no charge from within the "Supply and Demand" section of EPA's web site, http://clu-in.com (EPA 1997). (Allen 1997)

2.4 Remediation Technology Selection

Captain Allen discussed three decision matrixes currently used by the Air Force to determine the optimum technology to address the particular conditions at the site. Only the two that are used in future analysis will be commented on here.

DOD Treatment Technologies Screening Matrix

The Remediation Technologies Screening Matrix and Reference Guide provides a screening matrix for 55 different remediation technologies (see Table 2.1). These technologies have been evaluated based on the following factors: their development status and commercial availability, the residuals generated, the contaminants treated, reliability and maintainability, schedule, and cost. This guide is particularly helpful to the project manager faced with an unusual site or who wants to find an appropriate innovative technology (DOD 1994). (Allen 1997)

Air Force Center for Environmental Excellence Remediation Matrix

The Air Force Center for Environmental Excellence (AFCEE) has developed a decision-making tool entitled the Remediation Matrix-Hierarchy of Preferred Alternatives (see Table 2.2). This matrix provides a rank ordering of remediation alternatives for a given contaminant and zone of contamination (i.e. dissolved fuel in groundwater). This remediation matrix also provides a prioritized list of technologies to consider during project planning. Under a peer review system now in place in the Air Force, remediation managers who elect not to use AFCEE's recommended solution for a particular contamination scenario must specifically justify the use of another technology (Allen 1997).

The next section discusses the method of study for this research. The sequence of analysis, statistical analysis, and methods of handling data are presented in detail.




Table 2.1 DOD Technology Screening Matrix (DOD 1994)

4.50 Collictation Incament	Pilot	k	None	2		•	K	•	_	-			ORM
		1	200				1<		1			- -	14
1	ē	4	None	2		-	1		1				Velimer
4.32 Oxygen Enhancement with Air Sparging	Ē		None	ĝ			4						Nemer
4.33 Oxygen Enhancement with H ₂ O ₂	틸		None	ŝ			◁	•	✓	_		•	O&M
3.9 In Situ Physical/Chemical Treatment	\$1.00 PM												
4.34 Air Sparging	Full		Vapor	Υœ	7		◁	◁		_			Neither
4.35 Directional Wells (enhancement)	3		ž	Ž,		0	•	•	0	_		_	Neither
ł	13		Liquid, Vapor	۲ کو	\ 		4	4	0	_		9	O&M
1	3		Liauid		<		<	<	•				Neither
	Pilot	8	Liquid, Vapor	×S.			M	V	_			9	Š
1	Pilot	-	None	Yes			•	•				0	Neither
4.40 Passive Treatment Walls	Pilot	d	Selie	Ŷ		•			_	Ľ		_	CAP CAP
4.41 Slurry Walls (containment only)	Ξ		¥	¥	6	0	0	0					2
4.42 Vacuum Vapor Extraction	Pilot	<	Liquid Vapor No	ĝ			-	V			•	•	3
Ìφ				100 M				K	Å,				
4.43 Bioreactors	F		Solid	ŝ				•	_	۱	ź		ζV
3.11 Fr Str. Physical/Chemical Trestment (assuming pumping)													
4.44 Air Stripping	Full		Liquid, Vapor	ĝ		•		d		_	٧Z		O&M
	3		Selid	× ×	\ \	4		•					Neither
4.46 Ion Exchange	3		Solid	χœ	7	7		٥			•		Neither
4.47 Liquid Phase Carbon Adsorption	Ē		Տ	ŝ		•	•				ź	Ø	O&M
4.48 Precipitation	Ξ		S	ž	<u> </u>	4		-					Neither
4.49 UV Oxidation	3		None	ş			\triangleleft		7	_	¥	•	Both
3.12 Other Treatment		200		100 100 100 100 100 100 100 100 100 100									
4.50 Natural Attenuation	ž		None	S N			7	4					Neither
SEE MR IMISSIONS/OFF-GAS TREATMENT													
4.51 Biofiltration	Full	•	None		9		\vee	•	\mathbf{Z}	F	¥	-	Neither
1	Pilot	K	None					\vdash			×	•	_
1	Pilot	K	None	<u> </u>			K	•			¥	•	_
ŀ	12		None	_			M	•			¥		Neither
1	Fel		Solid								٧V		Neither
Rating Codes (See Table 3-1)													
Better I In	adedna	e Info	Inadequate Information										
• Average	Not Applicable	icable											
Works													


Table 2.1 DOD Technology Screening Matrix (Continued) (DOD 1994)

							,		Γ
	,		llesell The	LB) IN	auoz.	ACE POLICE IN THE POLICE IN TH	lateM Du	4	·
	John Wei John Vapor Tries John Vapor Tri	Whomost of the Mary of Tree Mand Williams of the Mary	Out By Sode Vin	BEODEN 11 SIGN DUNOS (11 JOSEP WANDER) 11 JOSEP WANDS	Pale	esopen ui sie	The many and a solution of the sument	S balking International Control of the Control of t	16
	Jeonen Jos	SIC DARWINOW.	TOMOS CHION	anossid oaku	N To	Now Mear	logen lod	POLEKOM,	
Natural Attenuation/Assimilation	-			-	-	-		-	
Bioventing	α,						:	4	
Soil Vapor Extraction	m				-		:	သ	
Heat Enhanced Vapor Extraction	4	; ;	4	-	-	:			
Low Permeability Cover/Cap	S.				က	1			
Excavate and/or Haul	9	1			4	4		80	
Composting (no tilling)								2	1
Land Farming				:		N		ဇ	:
Low Temp Thermal Desorp								9	1
Incineration (high temp)			:					7	i
Air Sparging			က	က					:
Passive Treatment Wall			4	4			ì		:
Conventional Pump and Treat			2	က					1
Slurry Wall			9	9				:	
Stabilization				S	N,	က	1		:
Permitted Direct Emission	:	-		!!	-		-		
Flare		:		1 .			2	:	
Biological Filter		4				:	9 •		
Catalytic Incineration		ο					4 1	:	
On-site Regenerative Polymer		m	:				ς.	:	
Carbon Adsorption		-					7	i	
Internal Combustion Engine		:			:	:	က		
GW Recirculation/Stripping		ro .	7	2					
This Matrix is an attemp to rank technologies/processes that should be considered for use at common Air Force sites. Managers should use this	jes/processes	that should be	considered fo	r use at comm	on Air Force s	sites. Manag	ers should us	se this	
hierarchy for screening technologies/processes and should be able to justify why a particular technology/process was selected over others with	esses and shou	uld be able to ju	ustify why a p	articular techno	ology/process	was selected	d over others	with	:
lower numbers. Certain categories of the	gories of the original Matrix were not used in this study and are not shown to enhance the clarity of the table	were not used	in this study	and are not sho	own to enhance	se the clarity	of the table.		
			:						

Table 2.2 AFCEE Remediation Matrix - Modified (AFCEE 1994)

Chapter 3 Study Methodology

The research procedure of the study is shown in Figure 3.1. Part I of this study was completed by Captain Scot T. Allen, 26 August 1997, and included project definition, literature review, data collection tool preparation, database



development and collection of U.S. Air Force data. His research plan for Part I is included in Appendix A. This thesis included additional data gathering from U.S. Navy sources and analysis. As mentioned in Part I, "Future refinement of this research could include the collection of data from the U.S. Army, other government agencies, or the private sector." (Allen 1997). In this chapter, data collection and analysis will be explained. Recommendations for future analysis will be addressed but specific issues and additional data collection will be fully addressed in Chapter 5.

3.1 Development of Data Gathering Tool - Project Survey

Captain Allen developed a data gathering tool, a "Project Survey", with input from professors in the faculty of Construction Engineering and Project Management, Environmental and Water Resources Engineering, and Geotechnical Engineering programs. His goals and objectives were to: 1) have a short survey so that respondents would not be dismayed at the task, and 2) to cover contamination type, geotechnical conditions, technology selected, reason technology was selected, contract type, duration and cost. Project managers were also asked to evaluate their projects considering cost and schedule performance and numerous subjective items. The target time to complete a survey was ten to fifteen minutes and feedback illustrated that this goal was met. This survey in included as Appendix B.

U.S. Navy data collection for Part II began in August 1997. After personally contacting project managers or their supervisors by telephone, approximately sixty-nine data collection surveys were distributed to twenty-three project managers by mail, e-mail, and facsimile. The data collection phase of this thesis was complete in mid-November 1997. Forty-six of the sixty-nine project

surveys had been returned by e-mail, mail, or fax and were incorporated into the database. Thus the response rate for the second phase of data collection was approximately 66.7%. The willing participation of numerous engineering field divisions and field activities far exceeded the goal of an additional thirty surveys for Part II of the study.

The combined data collection for both Parts I and II was very successful. Fifty-three survey respondents provided data on eighty-five environmental remediation projects. Twenty-one of the respondents requested a copy of the MS Access ® database. Summary tables of the data collected are included in Appendix C.

3.2 Development of a Relational Database

Captain Allen developed a relational database with which to store the project survey data. In Part I of this study, he details the concepts and design of the relational database that he developed using Microsoft ® Access Office 97 version. The query and interface capabilities of the Microsoft ® Office 97 suite later proved invaluable in data analysis.

3.3 Part I Hypotheses

In Part I, Captain Allen recommended the following hypotheses be tested:

- 1. Projects in which the guidance of the AFCEE remediation technology selection matrix is followed are more successful than those which do not;
- 2. The great majority (95%) of the technology selection decisions made in military projects are reasonable based on the site characterization;

- 3. Contract types which assign all risk to the contractor or owner are less successful than risk sharing contractual arrangements; and
- 4. One reaches a point of diminishing returns in site characterization and study, beyond which project success does not significantly improve.

Part II of the study tested hypothesis Number 1 above. This point correlates to Part II hypotheses Numbers 7 and 8. The remaining hypotheses from Part I are valid and form the nucleus for recommendations for future analysis, Section 5.2.

3.4 Part II Research Scope and Objectives

The scope of Part II of this research was to gather data from U.S. Navy project managers exercising in the field of environmental restoration and compliance.

Once the data was collected and organized it was structured for analysis and conclusions were made.

- Sixty-nine surveys sent to numerous Naval Facilities Engineering
 Command Engineering Field Divisions and Field Offices (Part II)
- Thirty-five Respondents queried (Part II)
- Forty-six Project Surveys returned (Part II)
- Total Respondents: Fifty-three (Parts I and II)
- Total Project Surveys: Eighty-five (Parts I and II)

The objectives of this research were to:

- Collect data from project managers
- Analyze data
- Formulate conclusions and recommendations
- Recommend future analysis

3.5 Data Collection from Project Managers

Project surveys were forwarded to Navy environmental remediation project managers by facsimile, e-mail, and mail after initial contact was made by telephone. Resident Officer in Charge of Construction (ROICC) field offices, Engineering Field Divisions (EFD) and the Navy Engineering Service Center were contacted. Several field offices referred to the Tulsa District, U.S. Army Corps of Engineers. The Army Corps readily responded and provided three project surveys from the Long Horn Army Ammunition Plant

3.6 Database Development

The data was entered into the MS® Access database created in Part I of the study. The data was queried and organized using the query functions of MS® Access and MS® Excel.

3.7 Data Analysis Correlations and Sequence

Figure 3.2 shows the data correlations that are analyzed in this thesis. The project survey generated numerous output variables correlated to project inputs. Input variables are independent of the process. In this thesis, environmental remediation project contaminant, remediation technology, contract type, and site geology are examples of input, or independent, variables. Output variables are dependent upon the process and one or more input variables. Examples in this study are project cost and schedule performance. The first step of analysis was to consider the overall evaluation of projects based on contaminant. Cost and schedule performance was then analyzed versus contaminant. A similar pattern of analysis was followed for "Technologies Selected" and "Reason for Technology

Selection". Conclusions were made based on data presented, comparisons between data sets and from Chi-Square analysis.

After the most significant categories for analysis were determined, the data was presented graphically in the eleven variable relationships shown in Figure 3.2. Statistical analysis followed. The hypotheses proposed are that relationships exist between input and output variables. For example, project cost and schedule performance as well as scope growth versus the type of contaminant, the remediation technology selected, and the reason for technology selection. The null hypotheses tested are that no such relationships exist. The chi-square statistic (χ^2) was used to test for the existence of a relationship between the variables.




Figure 3.2: Data Correlations Analyzed

The chi-square test is a very general test that is used to evaluate whether or not frequencies which have been empirically obtained, differ significantly from

those which would be expected. Contingency tables were then constructed illustrating the cross-classification of data. Table 3.1 is an example of a contingency table for "Cost vs. Contaminant". All of the contingency tables are included in Appendix D.

		Cost vs Contan	ninant			
Observed Freque	ncy					
	Chlorinated Solvents	Fuel Hydrocarbons	Metals	Other Contaminants	PCBs	Row Total
Over Budget	26.47	36.59	20.83	42.86	36.36	163.11
On /Under Budget	73.53	63.41	79.17	57.14	63.64	336.89
Column Total	100.00	100.00	100.00	100.00	100.00	500.00
Expected Frequer	ncy					
	Chlorinated Solvents	Fuel Hydrocarbons	Metals	Other Contaminants	PCBs	Row Total
Over Budget	32.62	32.62	32.62	32.62	32.62	163.11
On /Under Budget	67.38	67.38	67.38	67.38	67.38	336.89
Column Total	100.00	100.00	100.00	100.00	100.00	500.00
Chi-Square Terms	.					
	Chlorinated Solvents	Fuel Hydrocarbons	Metals	Other Contaminants	PCBs	
Over Budget	1.1600	0.4815	4.2601	3.2113	0.4292	
On /Under Budget	0.5616	0.2331	2.0626	1.5548	0.2078	
Chi-Square:	14.16					
Alpha:	0.001					
Critical Value:	18.4662					
Decision:	Accept Ho					

Table 3.1 Chi-Square Contingency Table

<u>Step One</u>: Compute the expected frequencies on the basis of the assumption that the variables are unrelated using the following formula:

 $f_e = \mbox{(column total * row total)/overall total}$ Where f_e is the expected frequency.

Step Two: Compute the chi-square terms table using the following formula:

$$\chi^2 = (f_o - f_e)^2 / f_e$$

Where fo is the observed frequency.

Step Three: Determine the chi-square approximation using the following formula:

$$\chi^2 = \sum (f_o - f_e)^2 / f_e$$

Step Four: Determine the critical chi value from a Chi-square distribution table or use the Microsoft ® Excel CHIINV function.

Step Five: Compare the critical chi value to the chi-square approximation determined in Step Three. Reject the null hypothesis if χ^2 is greater than the chi critical value. Do not reject the null hypothesis if χ^2 less than or equal to the chi critical value (Middleton 1995).

The null hypothesis of "no relationship" implies that each population will have the same proportions for each of the categories of the second variable.

Looking at the sampling distribution of chi-square can test the null hypothesis. If the value of chi-square is larger than expected by chance, the null hypothesis may be rejected. The significance levels presented indicate the error probability given that the null hypothesis is rejected. Thus smaller significance levels indicated the existence of a possible relationship (Blalock 1979).

3.8 Data Collection

The following is a discussion about the project survey development, data gathered using the project survey, and how it was adapted for analysis. The

background on several questions and the reasons for certain steps in data preparations are explained.

Captain Allen recommended in his thesis presentation that certain changes be incorporated in the project survey. The words "hazardous waste" were removed from the title to avoid confusion and sync with the Environmental Protection Agency's explicit definition. Since the word "failure" was considered to be "too strong" in the "key factors" question on the second page, the survey was changed to ask about the "impact of key factors on project outcome (1-positive, 2-no major impact, 3-negative, 4-N/A)." The final recommendation to number the questions on the survey was not incorporated and was never an issue. The discussion continues with background information for one survey question.

The project survey question "What is the primary reason (or combination of reasons) for technology selection?" offered six selections for the respondent to choose. The first one was "Air Force Guidance" which correlates to the first hypothesis in Part I of this study: "That projects in which the guidance of the AFCEE remediation technology selection matrix is followed are more successful than those which do not." Part II of the study focused on data collection from the U.S. Navy so the response selection on the survey was changed to read "NAVFAC Guidance." NAVFAC does not utilize the Air Force decision selection matrix so the response to this question could not be combined into an overall category such as "Sponsor Guidance." NAVFAC has a general policy that innovative technologies should be utilized in an effort to optimize schedule and cost performance but does not adhere to a strict decision matrix (DON 1996). Thus, this study will address the use of the AFCEE remediation technology decision matrix and its effectiveness as a primary reason for technology selection. The next two sections will describe data that fell into the "Other" categories.

The "Other Technology" category has twenty-six projects in it. Five of the projects used a combination of technologies generally associated with land disposal. This category of "Other Technologies" includes many innovative means for environmental clean up and compliance, including: underground storage tank and fuel piping removal, resin adsorption vapor treatment, base catalyzed decomposition, and recycling various material for asphalt concrete.

The "Other Contaminants" category is associated with fifteen projects. Seven projects have one type of contamination not falling into one of the four major categories while eight have a combination of contaminants. Generally, the "Other Contaminants" are: pesticides, low level radioactive waste, lead, asbestos, and explosives.

Data was arranged for graphical presentation increasing from left to right with the "good" category in the series to the rear. The author did this since the "good" category was almost always numerically greater than the "bad" category and the graph was therefore easier to read. The "good" category is typically series such as "On Budget", "Ahead or On Schedule", or "Successful". The next two sections discuss data not utilized due to insufficient sample size and grouping data into larger categories.

Some data could not be analyzed due to insufficient response in that particular category. Respondents were given full latitude to select the projects that they reported on although they were requested to try to give a quality spread with one project considered highly successful, one project considered typical, and one project below their expectations. Several of the remediation technology categories did not have enough data to be statistically valid.

Technologies dropped include:

Passive Treatment Wall

Bioventing

Chemical Oxidation / Reduction

Incineration

Much of the data gathered on the Project Survey was suitable for grouping prior to analysis. The data was grouped for several reasons. First, there was a very fine line in distinction between alternatives for respondents to select on some of the subjective questions. And second, grouping simplified and clarified analysis. Three categories of data were grouped during this analysis: 1) "Successful" and "Acceptable" were grouped in the project's overall assessment. This was grouped because the survey did not present sufficient ranking criteria or structure to differentiate the two. Additionally, "Acceptable" implies a success... the two are very nearly the same. 2) "Ahead" and "On schedule" were grouped because "On schedule" is good and "Ahead of schedule" is generally accepted as good also. 3) "No change" and "Decreased scope" were grouped because "No change" in scope suggests that the scope definition was good and "Decreased scope" is generally accepted as good.

The data collection tool, while itself concise, generated far more areas of study than can be adequately addressed in one thesis presentation. The data collected are included in Appendix C. The names and telephone numbers of the individual survey participants are not provided in this thesis for confidentiality. The next two sections propose future analysis. The first section centers on a wealth of subjective data on factors impacting project outcome. The respondent was requested to rank fourteen items one to four using the following scale:

1 – Positive

2 - No major impact

3 – Negative

4 - Not applicable

The second section is a good follow-on to analysis in this thesis considering contract issues, geotechnical issues, and clean-up standards versus overall success, cost and schedule performance, and scope change.

3.9 Recommended Future Analysis

Data items not considered in this analysis but reserved for possible future analyses include the following:

Input Variables

Output Variables

Sources of funding

Operations and maintenance costs

Estimated contract cost

Percentage complete (to date)

Project duration

Reuse plans for the site

Impact on project outcome

- Project planning / Funding
- Political involvement
- Laboratory analysis / Sampling plan & methods
- Implementation contract type / Contractor performance
- Team building & partnering / Contract disputes
- Severe weather / Contract incentives
- Discovered more contamination
- Unanticipated soil, geological or ground water conditions
- Technology performance

Data analyses considered particularly valuable but reserved for future analyses are shown in Figure 3.3. The entire spectrum of contract type is useful




Figure 3.3: Correlations Recommended for Future Analyses

to consider when faced with an environmental compliance requirement. Ground water and site geology analysis could yield indicators of success in one remediation technology over another. The clean-up standards that are applied by various agencies vary, can affect project success, and are certainly worthy of analysis. The evolution of site characterization costs is valuable to consider for many reasons. One could determine whether there are trends over the past fifteen to twenty years showing that pre-project planning is paying off and in what particular arena. Perhaps more importantly, one may determine if the Department of Defense is getting better at dealing with environmental issues.

The next chapter covers data analysis. Again, Figure 3.2 illustrates the sequence of analyses and is a ready reference guide through Chapter 4.

Chapter 4. Data Analysis

4.1 Project Performance versus Contaminant

The vast majority of the projects, 97.7% were evaluated as successful. As shown in Figure 4.1, only two of eighty-five projects in the sample were rated unsuccessful.




Figure 4.1: Overall Performance vs. Contaminant Type

The overwhelming survey response with successful projects may in part be due to respondents' natural tendency to report on successes rather than failures even though a quality spread was requested. Table 4.1 details contaminant type in the unsuccessful projects. Project "A" had fuel hydrocarbon contamination and Project "B" had a combination of fuel hydrocarbon, chlorinated solvents, and metals. Both projects were over-budget, behind schedule, and their scope

increased. The final question on the project survey was an overall evaluation of the project results to date. The respondent was given three categories from which to select a response:

- Successful
- Acceptable
- Unsuccessful

As discussed in Section 3.7, "Successful" and "Acceptable" were grouped together to clarify analysis. In retrospect, providing a better metric for response to this question would have significantly increased the value of the data. The following two sections show that while, for the data gathered, fuel hydrocarbons were present in a significant number of projects associated with poor cost and schedule performance, statistical analysis shows in both cases that there is no relationship between cost or schedule performance and contaminant type.

Contaminant Present	Unsuccessful Project "A"	Unsuccessful Project "B"
Other Contaminants (n=14)		
Fuel Hydrocarbons (n=41)	X	x
PCBs (n=11)		
Chlorinated Solvents (n=34)		X
Metals (n=24)		x

Table 4.1: Contaminants Present in Unsuccessful Projects

4.2 Cost Performance versus Contaminant

The data shown in Figure 4.2 suggest that there are few budget certainties in environmental restoration and compliance projects.




Figure 4.2: Cost Performance vs. Contaminant Type

Overall twenty-nine of the eighty-five, or 34.1% of the projects sampled were over budget. Projects with metal contaminants performed best. Both "Fuel Hydrocarbons" and "Other Contaminants" categories performed lower than average for the sample set when considering cost performance. While graphically it appears that projects with metal contaminants perform better than other contaminants, chi-square statistical analysis shows that project cost performance in general *does not* vary with contaminant type. The contingency tables that

support the chi-square analysis of the null hypothesis are included in Appendix D, Table D-1.

Specific observations include the following:

- Metals Five of twenty-four or 20.8% over budget
 - Associated data show that scope increased on four of the five projects over budget.
- Fuel Hydrocarbons Fifteen of forty-one, or 36.6% over budget
 - Scope increased on seventeen of the forty-one projects. Not all of the budget overruns are possibly attributed to scope growth though as only twelve of those were over budget (29.3% of the total).
- Other Contaminants Six of fourteen or 42.9% over budget
 - Scope increased on nine of fourteen projects, six of which were over budget (42.9% of the total).
 - As discussed in Section 3.8, contaminants in this category include pesticides, low level radioactive waste, lead, asbestos, and explosives which coupled with scope growth may explain the over-budget cost performance.

4.3 Schedule Performance versus Contaminant

The data shown in Figure 4.3 suggests that four of the five categories performed satisfactorily "Ahead or On Schedule" 73% to 82% of the time. Overall sixty-three of the eighty-five, or 74.1% of the projects sampled were "Ahead or On Schedule" schedule. "Chlorinated Solvents" were the best performers while both the "Fuel Hydrocarbons" and the "Other Contaminants" categories performed lower than average for the sample set. While graphically it

appears that projects with chlorinated solvent contaminants perform better regarding schedule than other contaminants, chi-square statistical analysis shows that project schedule performance in general *does not* vary with contaminant type. The contingency tables that support the chi-square analysis of the null hypothesis are included in Appendix D, Table D-2.




Figure 4.3: Schedule Performance vs. Contaminant Type

Specific observations include the following:

- Chlorinated Solvents Six of thirty-four or 17.7% behind schedule.
 - Four of these six had scope growth.

- PCBs Two of eleven or 18.2% behind schedule.
- Metals Six of twenty-four or 25% behind schedule.
- Fuel Hydrocarbons Eleven of forty-one or 26.7% behind schedule.
- Other Contaminants Six of fourteen or 42.9% behind schedule.
 - Scope increased on nine projects, six of which were over budget (42.9% of the total).
 - As discussed in Section 3.8, contaminant types in this category include pesticides, low level radioactive waste, lead, asbestos, and explosives which coupled with scope growth may explain this over budget cost performance.

4.4 Project Performance versus Technology Implemented

The project survey identified eleven specific environmental remediation technologies and allowed the respondent to pencil in any additional innovative technologies that may have been utilized:

Soil vapor extraction Passive treatment wall

Air sparging Low permiability soil cap

Biodegradation Goundwater pump and treat

Bioventing Excavation and incineration

Chemical reduction / oxidation Excavation and land disposal

Composting And several innovative technologies

Bioventing, composting, treatment wall, incineration, and chemical oxidation / reduction are not considered in this study due to insufficient sample population in

the response to the survey. Project cost and schedule performance as well as scope change and overall evaluation will be addressed in this section.

4.5 Overall Project Evaluation versus Technology Implemented

All but two of the eighty-five projects surveyed were judged by the survey respondents to be successful.




Figure 4.4: Overall Project Results vs. Technology Implemented

One soil vapor extraction project and one pump-and-treat project were over budget, behind schedule, and increased in scope more than 5%. Their project manager judged both projects unsuccessful. As discussed in Section 4.1,

clearer definition of a more refined metric would have produced more valuable data in this category. Figure 4.4 displays this data graphically.

4.6 Cost Performance versus Technology Implemented

Figure 4.5 illustrates that seven of eight remediation technologies performed well being on or under budget between 66.7% and 100% of the time.




Figure 4.5: Cost Performance vs. Technology Implemented

"Composting" performed poorly with all four of the projects in the sample group over budget. While four projects in each category is a small sample size, two technologies stand out in their cost performance. "Air Sparging" performed

particularly well with dissolved fuel or dissolved chlorinated solvents in ground water and "Composting" performed poorly from the sample set with fuel contaminated soil. Statistical analysis supports the graphical representation in Figure 4.5 that suggests that some remediation technologies are better than others in cost performance. Chi-square analysis rejects the null hypothesis and supports the alternate hypothesis that project cost performance *does vary* with technology implemented. The contingency tables that support the chi-square analysis of the null hypothesis are included in Appendix D, Table D-3.

- "Soil Vapor Extraction" Two of twelve or 13.7% of the projects were over budget.
- The best performer was "Air Sparging" with 100% of the four projects on or under budget.
- All four projects utilizing "Composting" were over budget.
 - Associated data shows that three of the four projects were also behind schedule and three of the four (not the same three) increased in scope more than 5%.
- "Low Permeability Soil Cap" Two of the six, or 33.3% of the projects were over budget.
- "Other Technologies" Four of thirteen or 30.8% of the projects were over budget.
 - As described in Section 3.8, often developing or innovative technologies
 were in this category. Five such projects which were a combination of
 technologies generally associated with land disposal and underground
 storage tank and fuel piping removal, resin adsorption vapor treatment,

base catalyzed decomposition, and recycling various material for asphalt concrete were over budget.

4.7 Schedule Performance versus Technology Implemented

The data in Figure 4.6 illustrates that five of the eight remediation technologies performed well being ahead or on schedule between 76.9% and 100% of the time.




Figure 4.6: Schedule Performance vs. Technology Implemented

Land disposal and biodegradation were the top performers while soil vapor extraction, composting, and air sparging were the poorest. Statistical analysis

supports the graphical representation in Figure 4.6 that suggests that some remediation technologies are better than others in schedule performance. Chisquare analysis rejects the null hypothesis and supports the alternate hypothesis that project schedule performance *does vary* with technology implemented. The contingency tables that support the chi-square analysis of the null hypothesis are included in Appendix D, Table D-4.

Specific observations include the following:

- Nine of the ten "Land Disposal" and five of five "Biodegradation" projects were ahead or on schedule.
- "Composting" Three of the four, or 75%, of the projects were behind schedule.
- "Air Sparging" Two of the four, or 50%, of the projects were behind schedule.
- "Soil Vapor Extraction" Five of the twelve, or 41.7%, of the projects were behind schedule.

Schedule and cost performance on the four projects utilizing "Composting" may be tied together. All four projects were over budget and three of the four were behind schedule.

4.8 Scope Change versus Technology Implemented

The data in Figure 4.7 illustrates that project scope increased between 30% and 50% in the best performing six remediation technologies implemented. The series displayed in Figure 4.7 is bracketed by two technologies that had a much smaller sample size of four projects each. While four projects in each category is

a small sample size, two technologies stand out in their change in scope. "Air Sparging" performed particularly well with dissolved fuel or dissolved chlorinated solvents in ground water and "Composting" performed poorly from the sample set with fuel contaminated soil. Statistical analysis supports the graphical representation in Figure 4.7 that suggests that some remediation technologies are better than others in scope change. Chi-square analysis rejects the null hypothesis and supports the alternate hypothesis that project scope change does vary with technology implemented. The contingency tables that support the chi-square analysis of the null hypothesis are included in Appendix D, Table D-5.




Figure 4.7: Scope Change vs. Technology Implemented

- "Air Sparging" One of four, or 25% of the projects increased in scope.
- "Land Disposal" Three of ten, or 30% of the projects increased in scope.

- "Pump and Treat" Six of thirteen, or 46.2% of the projects increased in scope.
- "Soil Vapor Extraction" Six of twelve, or 50% of the projects increased in scope.
- "Composting" Three of four, or 75% of the projects increased in scope.

4.9 Performance versus Reason for Technology Selection

This section presents an analysis of project performance in cost, schedule, scope change, and overall success versus the reason the program manager selected the particular remediation technology. The survey addressed six major reasons why program managers selected a specific remediation technology:

- Selection may be based on guidance from AFCEE or NAVFAC.
- "Regulatory requirements" may dictate a specific technique.
- "Minimal Exposure Hazard" may be a concern.
- "Cost"minimization.
- "Schedule" maintainability or quick turn-around.
- "Effectiveness" of the technology.

Section 3.8 covers in detail what is meant by AFCEE or NAVFAC guidance. The Air Force has developed a decision matrix for remediation technology selection. Part of this study is to validate that matrix.

4.10 Overall Project Evaluation versus Reason for Technology Selection

The project survey queried the respondent's "Evaluation of overall project results to date" and allowed the respondent to select one of three categories: a) Successful, b) Acceptable, or c) Unsuccessful.




Figure 4.8: Overall Results vs. Reason for Technology Selection

Figure 4.8 illustrates overall project results versus each of the six categories that survey respondents selected as the primary reason or combination of reasons for technology selection. All six categories were graded exceptionally well. Overall there were only two of eighty-five projects or 2.4% marked unsuccessful. Each of these projects was behind schedule, over budget, and the scope had increased.

The data supports the first hypothesis from Part I of this study, but overall the results may be inflated. Grade inflation may be a combination of an insufficient scale on the project survey attempting to quantify this subjective data and the survey respondents desire to inflate overall project evaluation. It is only natural to want to point out one's successes rather than one's lesser performance.

When schedule, cost, and scope are considered with the overall project evaluation, from a combined perspective, the data supports: "that projects which utilize the AFCEE remediation technology selection matrix were more successful than those which do not". As discussed in Sections 4.1 and 4.5, clearer definition of a more refined metric would have produced more valuable data in this category.

4.11 Cost Performance versus Reason for Technology Selection

The project survey queried project cost and allowed the respondent to select one of three categories: a) Under budget (2% or more), b) On budget, or c) Over budget (2% or more). Figure 4.9 illustrates cost performance versus each of the six categories that survey respondents selected as the primary reason or combination of reasons for technology selection. Generally, five categories performed in an acceptable range being on budget between 67.6% and 75% of the projects studied. When "Schedule" was selected as a reason for the project's technology selection, the overall results were below average. Graphically it appears that projects, which used AFCEE guidance or effectiveness to select the remediation technology to be implemented, performed best regarding cost. Chisquare statistical analysis shows that project cost performance in general *does not* vary with reason for technology selection. The contingency tables that support the chi-square analysis of the null hypothesis are included in Appendix D, Table D-6.




Figure 4.9: Cost Performance vs. Reason for Technology Selection

- When "Schedule" was selected as a reason for the project's technology selection, projects were only on budget 10 of 17 or 58.8% of the time.
 - Project duration or schedule may have been more important than cost and the project manager may have allowed the cost to creep up in order to maintain schedule.
- When "Cost" was a technology selection criteria, projects came in on budget 67.6% of the time.
 - Twenty-one of the thirty-eight projects addressed fuel hydrocarbon or a combination of fuel and other contaminants. Eight of twelve, or 66.7%, of the over budget projects were to remediate fuel contamination.
 - Four of the twelve, or 33.3% of the over budget projects were to remediate chlorinated solvents.

- "Composting" and "Land Disposal" were the predominant remediation technologies in these projects.
- When "Regulatory Requirements" was a technology selection criteria, projects came in on budget 69.2% of the time.
- When "Minimal Exposure Hazard" was a technology selection criteria, projects came in on budget 72.3% of the time.
- "Effectiveness" of the technology is probably the strongest selection reason with 72.9% of the large, 48 project, sample being on budget.
 - This reason was most often cited as the reason that a project manager selected a particular technology. "Effectiveness" was selected 56.5% of the time.
 - When the technology is selected based on how well it performs, tried and true methods deliver in the majority of the cases sampled.
- Projects that utilized the AFCEE technology selection matrix in determining which remediation technology to utilize were successfully on budget 75% of the time.

Using the AFCEE selection matrix as the primary reason for technology selection was the best overall selection criterion for this data sample. This area of analysis confirms part of the first hypothesis from Part I.

4.12 Schedule Performance versus Reason for Technology Selection

The project survey queried project schedule performance and allowed the respondent to select one of three categories: a) Ahead of schedule (2% or more), b) On schedule, or c) Behind schedule (2% or more).




Figure 4.10: Schedule Performance vs. Reason for Technology Selection

The data illustrated in Figure 4.10 shows schedule performance versus each of the six categories that survey respondents selected as the primary reason or combination of reasons for technology selection. Generally, all six categories performed in an acceptable range being on schedule between 73.7% and 90.9% of the projects studied. Graphically it appears that projects, which used minimal exposure hazard or AFCEE guidance to select the remediation technology to be implemented, performed best regarding schedule. Chi-square statistical analysis shows that project schedule performance in general *does not* vary with reason for technology selection. The contingency tables that support the chi-square analysis of the null hypothesis are included in Appendix D, Table D-7.

- The most outstanding categories in this sample were "Minimal Exposure Hazard" and "AFCEE Guidance" which were ahead or on schedule 90.9% and 87.5% for the eleven and eight projects respectfully. When the program manager selected a remediation technology to address one of these criteria, he was typically dealing with the following type projects:
 - Six of the eight projects that utilized the "AFCEE Guidance" had fuel hydrocarbon or a combination of fuel and other contaminants.
 - The Air Force projects did not utilize "Composting" but used "Soil Vapor Extraction", "Biodegradation", "Bioventing", and in one case "Land Disposal".
 - Six of the eleven projects, or 55%, that utilized the "Minimal Exposure Hazard" "as a remediation technology (and used "Cost" as a technology selection criterion) addressed a chlorinated solvent contamination. Four of these six, or 36% of the projects were for metal contamination. Land disposal or soil cap were used almost exclusively.
- Projects that selected a technology specifically for "Schedule" concerns came
 in ahead or on schedule fourteen of seventeen or 82.3% of the time ranking
 third overall.
- The low end of the spectrum were projects with technology selected based on "Cost" which still produced a satisfactory twenty-eight of thirty-eight or 73.7% ahead or on schedule. When the program manager selected a technology based on cost control, there are several reasons that relate to poor schedule performance:
 - Twenty-one of the thirty-eight projects that were behind had fuel hydrocarbons or a combination of fuel and other contaminants. Six of these twenty-one, or 29% were behind schedule.

- Four of the ten projects that were behind schedule were utilizing innovative technologies. Two of these projects were using processes that are preliminary to "Composting".
- Three of four projects, or 75%, that utilized "Composting" as a remediation technology (and used "Cost" as a technology selection criterion) were behind schedule.
- Three of seven projects, or 40%, that utilized "Soil Vapor Extraction" as a remediation technology (and used "Cost" as a technology selection criterion) were behind schedule.

This data suggests that "Composting" does not have as effective cost control as other remediation technologies and is a slower process than originally programmed thus additional time is required during project execution. "Composting" should not be selected as a remediation technology if schedule and cost are important. This data is also associated with analysis in Section 4.7 showing "Soi! Vapor Extraction" projects to be behind schedule on five of twelve, or 41.7% of the time. This correlation suggests that while "Soil Vapor Extraction" is a good performer for cost control, it is not good in schedule performance.

Using the AFCEE selection matrix as the primary reason for technology selection was a strong performer for this data sample. This area of analysis confirms part of the first hypothesis from Part I.

4.13 Scope Change based on Reason for Technology Selection

The project survey queried project scope change and allowed the respondent to select one of three categories: a) Increased scope (5% or more), b)

No change, or c) Decreased scope (5% or more). The data in Figure 4.11 illustrates scope change versus each of the six categories that survey respondents selected as the primary reason or combination of reasons for technology selection. Scope change is common place in environmental remediation projects due to the inherent uncertainty associated with unknown and underground conditions. A project whose scope increases is not necessarily considered unsuccessful. In fact, the scope increased on fifty-two of eighty-five or 61.2% of the projects surveyed yet only two projects were reported unsuccessful. Statistical analysis supports the graphical representation in Figure 4.11 suggesting that some reasons for selecting a remediation technology are better than others in scope definition. Chi-square analysis rejects the null hypothesis and supports the alternate hypothesis that project scope performance *does vary* with reason for technology selection. The contingency tables that support the chi-square analysis of the null hypothesis are included in Appendix D, Table D-8.

- Both of the unsuccessful projects were over budget, behind schedule, and the scope increased.
- Scope control as an output of the reason for technology selection is best afforded when "Schedule" or "Effectiveness" of technology is most important.
 - "Effectiveness" Three of forty-eight, or 6.25% increased scope.
 - "Schedule" Three of seventeen, or 17.7% increased scope.
- "AFCEE selection criterion" two of eight, or 25% increased scope.
- "Cost" Nineteen of thirty-eight projects, or 50% increased in scope.




Figure 4.11: Scope Change vs. Reason for Technology Selection

This may not be cause for alarm when correlated with other survey data.

None of the projects marked "unsuccessful" by survey respondents used cost as a primary reason for technology selection. Only nine of the nineteen projects that experienced scope growth were over budget. In this category there are thirty-eight projects which considered "Cost" as a primary reason for technology selection. Nine projects, or 23.7% experienced scope growth coupled with being over budget. This cost performance coupled with scope increases is considered to be within satisfactory bounds. When the overall project rating and budget concerns are considered in concert with the scope change, the data suggests that project controls were successful when "Cost" was considered important. The next chapter presents the study conclusions and recommendations.

Chapter 5 Conclusions and Recommendations

5.1 Conclusions

This chapter completes the study by summarizing the hypotheses and then presentation of conclusions and recommendations. The following hypotheses were proven in this thesis:

- 1. That project cost performance does vary with technology implemented.
- 2. That project schedule performance *does vary* with technology implemented.
- 3. That project scope performance does vary with technology implemented.
- 4. That project scope performance *does vary* with reason for technology selection.

This thesis demonstrates that steps in planning environmental restoration and compliance projects can increase the likelihood of successful project performance. Specifically, careful consideration of the reason for technology selection and the actual technology selected can greatly effect project outcome in schedule and cost performance. Both the Department of Defense Technology Selection Matrix and the Air Force Center for Environmental Excellence Remediation Matrix are effective decision making tools to help select the appropriate remediation technology although they do not in themselves guarantee success. These tools are certainly recommended for the inexperienced project manager. Additional hypotheses also proven in this thesis follow:

- 5. That project cost performance does not vary with contaminant type.
- 6. That project schedule performance does not vary with contaminant type

- 7. Project schedule performance *does not vary* with reason for technology selection.
- 8. Project cost performance *does not vary* with reason for technology selection.

The following conclusions are in addition to the proven hypotheses:

- 1. That in general the AFCEE selection matrix is a valuable tool in determining which remediation technology to utilize.
- 2. That while the Air Force pushes composting in the AFCEE matrix it was a poor performer in this sample group.

5.2 Recommendations

The following recommendations were developed during analysis and evaluation in this thesis:

- 1. That further study be conducted using the abundant, valuable data already gathered on the project survey and formulated in the database. The most valuable data relationships to consider are shown in Figure 3.3. Contract type, groundwater problems, applicable clean-up standards, technology compared to geology, and site characterization study costs can all be compared to overall project success, project cost and schedule performance, and project scope changes.
- 2. That additional data should be gathered to specifically address the question of DOD performance in site characterization. A study of the evolution of site characterization costs could determine whether there are trends over the past fifteen to twenty years showing that pre-project

planning is paying off and in what particular arena. More importantly, one may determine if the Department of Defense is getting better at dealing with environmental issues and also whether the costs of the study produce sufficient benefit to justify continued expenditures.

- 3. That should additional data be gathered using this project survey tool or one similar to it, the question of an overall project evaluation should be refined and a better metric should be developed. The metric could build on a scale of one to five and give quantifiable items for the respondent to consider. Successful projects would be graded five and unsuccessful projects graded one. Acceptable projects would be defined as a grade of three. The respondent would be asked to subtract one point if the project was behind schedule 2% or more and subtract one point if the project was over budget 2% or more. Other similar quantifiable items could be defined or the balance of the grade could be left to the respondent's subjective evaluation. The end result would be much more valuable data for project performance analysis.
- 4. That a systems engineering approach should be used in the remediation technology selection process. That is, decisions should be made using some sort of proven decision-making matrix such as the Department of Defense Remediation Technologies Screening Guide, Table 2.1 or the Air Force Center for Environmental Excellence Remediation Matrix-Hierarchy of Preferred Alternatives, Table 2.2. Both tables have been developed with process improvement and feedback loops to self-improve.

This concludes the written portion of this thesis. Following are various appendices including data and analysis tables, then bibliography, and vita.


Appendices

A.	Research Plan from Part I	50
В.	Data Collection Tool	52
C.	Data Collected	55
D.	Chi-square Contingency Tables	91

Appendix A

Research Plan from Part I

The following figure is the work of Captain Scot T. Allen USAF.



Appendix B

Data Collection Tool

The following survey is the work of Captain Scot T. Allen USAF.

Please fill out and return to: LT Joseph A. Campbell
Department of Civil Engineering, CEPM
jacampbell@mail.utexas.edu
The University of Texas
Austin TX 78712-1076

Tel: (51:
E-mail:
Fax: (51:

Tel: (512) 331-8899

Fax: (512) 471-3191

Environmental Site Remediation Project Survey

Name:	Fax:	Date:
Agency/Unit:	Project Na	me:
Telephone:		cation (Base, City, State):
E-mail:		
	m Dushlama	
Contaminants present (check all that apply): Fuel hydrocarbons Chlorinated solvents Metals PCB's Other: Maximum depth of contamination: 0-10 feet 11-20 feet 21-30 feet 31-40 feet 41-50 feet Over 50 feet Contamination has affected (all that apply): Soil Groundwater Air If groundwater is affected, contaminants are (ch that apply): Dissolved in groundwater Free product (Non-Aqueous Phase Liquid, NAPL)	Average Geature Consider the Consideration the Con	ndwater is affected, the plume: extends beyond the property line is completely on site has an unknown extent te depth to the water table: 0-10 feet 11-20 feet 21-30 feet 31-40 feet 41-50 feet Over 50 feet ology classification (check the most important sites): Tight clay/silt (impermeable soils) Loose sand/gravel (permeable soils) Relatively impermeable bedrock (e.g. solid granite) Permeable bedrock (e.g. fissured limestone) planned for reuse: In 1-3 years In 4-10 years No definite plans (or no information)
Remediation technology selected (please indicate combinations): Soil vapor extraction (SVE) Air sparging (in situ) Biodegradation (except bioventing) Chemical Oxidation/Reduction Composting or Land Farming Excavation and land disposal Excavation and incineration Low Permeability Soil Cap Passive Treatment Wall Pump and treat (ex situ air stripping) Other:	Primar was sel	plicable clean-up standards: Non-detect level Background level Risk based clean-up level Federal or state remediation standard v reasons this technology (or combination) ected: NAVFAC guidance Cost Schedule Regulatory requirements Effectiveness Minimal exposure hazard Other:

	Defense Environmental Restoration	on
Source(s) of funding:	Account (DERA)	
Base realignment and closure (BRAC) Installation Restoration Program (IRP)	Other:	
Installation Restolation Program (24)		
The Co	ontract:	
Type of remediation implementation contract:	Design and construction were done by	:
☐ Firm fixed-price (lump sum)	☐ Separate contracts	
Cost reimbursable (cost plus)	In-house design and separate construction contract	
☐ Unit price	Design-build contract	
Other:	Design-bund contract	
	What percentage of the implementation	n project has
Estimated total contract cost amount (investigation,	been completed to date:	
implementation, monitoring):	□ 0-25%	
	26-50%	
Implementation contract project duration	51-75%	
(months):	76-100 %	
(1000-1)	Project complete	
	to Date: Impact on project outcome (1-Positive	
Project scope change during project:	2-No major impact, 3-Negative, 4-N/A	A):
☐ Increased (5% or more)	2-140 major mipassa 5 - 1-5	1234
☐ No change	Project planning	
Reduced (5% or more)	Sampling plan/methods	0000
Business seems	I aboratory analysis	
Project cost: Q Under budget (2% or more)	Implementation contract type	
On buaget	Contract incentives	
Over budget (2% or more)	Contract penalties Team building/partnering	
	Contractor performance	0000
Anticipated or actual annual operations and	Contractor performance Contract disputes	
maintenance (O&M) cost:	Discovered more contamination	
construction comment on Site	Unanticipated soil, geological,	
Percentage of total project cost spent on site characterization and study:	or groundwater conditions	
characterization and study.	Technology performance	
Schedule performance:	Severe weather (force majeure)	
Ahead of schedule (2% or more)	Funding Political involvement	
On schedule	Other:	0000
☐ Behind schedule (2% or more)		
(a is married) semilatory	Evaluation of overall project results to	I CIALC:
Project met (or is meeting) regulatory	Successful Acceptable	
remediation goals:	Unsuccessful	
U 16		
- ·	U lun desphase? □Yes □No	
Would you like a disk copy of the Microsoft Access for V	Vindows database:	
Other comments on the project (or any of the questions a	bove):	
Please recommend another person who could contribute	to this research by filling out project inform	nation
Please recommend another person who could contribute	IV Many	
surveys: E-mail:	Tel:	•
Name: E-mail:	Fax:	
Address	rax:	

Appendix C

Data Tables

Table C-1	Project Name and Location - Data Table	56
Table C-2	Project Contaminant and Comments – Data Table	5 9
Table C-3	Project Reason for Technology Selection and Applicable Clean-up)
	Standards - Data Table	64
Table C-4	Project Results - Data Table	68
Table C-5	Contract Type and Cost – Data Table	72
Table C-6	Contract Funding and Performance – Data Table	76
Table C-7	Extent of Contamination – Data Table	8 0
Table C-8	Regulatory Goals and Remediation Technology	83
Table C-9	Site Geology	87

Project		Respondent			
- ₽	Project Name	<u>0</u>	Base	City	State
သ	Small Arms Firing Range	-	Bergstrom AFB	Austin	Ϋ́
9	Oil Water Separator Removal	-	Bergstrom AFB	Austin	Ϋ́
7	Air Injection/Soil Vapor Extraction	8	Bergstrom AFB	Austin	ĭ
80	Landfills 3-7	1	Bergstrom AFB	Austin	ĭ
6	Facility 4537, JP8 PST Removal	1	Bergstrom AFB	Austin	¥
9	Base Boundary Pump and Treat	4	Norton AFB	Sacramento	გ
1	Site 1 Removal Action	4	Norton AFB	Sacramento	δ
12	TCE Soil Vapor Extraction	4	Norton AFB		Ą
13	Excavate Landfill 5	5	Pease AFB		Į
4	Hydrant System Removal	5	Pease AFB		Į
15	Hydrant System Site Characterization	5	Pease AFB		ĭ
16	Site 8 Remedial Action	5	Pease AFB		王
17	Spill Site 10	5	Plattsburgh AFB		Ν
18	Boundary Area Hydraulic Containment Sys	9	Lowry AFB	Denver	္ပ
19	Reactive Wall	9	Lowry AFB	Denver	8
20	Source Area TCE Plume	9	Lowry AFB	Denver	္ပ
21	Bioventing at Sites STO 7 and STO 9	9	Lowry AFB	Denver	္ပ
22	Landfill Cap (OU 2)	9	Lowry AFB	Denver	႘
23	Fire Training Area #2	2	Chanute AFB	Rantoul	اد
24	Building 700 groundwater		Chanute AFB	Rantoul	ᆜ
25	Low Level Radioactive Waste Removal	8	Bergstrom AFB	Austin	¥
5 8	Area 1 TCE Plume	6	Bergstrom AFB	Austin	ĭ
27	SWMU 9 Fire Department Training Area	6	Bergstrom AFB	Austin	ĭ
78	SWMU 121/205 Firing Ranges	6	Bergstrom AFB	Austin	¥
29	Site 29, SVE for Vadose Zone	10	Mather AFB		CA
30	Landfills 2-6	10	Mather AFB		CA
31	Site 32, UST	10	Mather AFB		δ
32	Unnamed Stream	11	Carswell AFB	Ft. Worth	ĭ
33	SVE at IRP sites 1, 2, 3	12	AFP 44	Tucson	AZ

Table C-1 Project Name and Location

		Recoondent			
nafora l		2		, tr	State
<u>_</u>	Project Name	2	Dase	CIS	2 24
34	Hazardous Waste Storage Area Closure	13	Griffiss AFB	коше	2
-	Remove USTs	13	Griffiss AFB	Rome	×
Ì	Site 1	14	Vandenburg AFB		ح ک
ļ	Auto Hohby Shop Soils	9	Lowry AFB	Denver	8
3	Site 29 SVF/Bioventing	15	Mather AFB		₹
3 2		16	Homestead AFB	Homestead	긥
A 0	er Po	20	NETC	Newport	æ
4	NAS-1 Wellhead Treatment System	21	NAS Agana	Guam	Marianas Islands
42	TPH Soil Remediation	22	Midway Island		
43	RAC II Delivery Order 7	23	NAS Kingsville	Kingsville	¥
44	DO 1 SOW 5	24	NAS	Corpus Christi	¥
45	DO 16 SOW 24	24	NAS	Corpus Christi	¥
Ye e	Area "A" I andfill Can	25	NSB	New London	CT
47	NAWC Trenton	26	Ewing TWP	TWP	3
48	Site 2 Fire Training Area	27	NWIRP	Calverton	
49		28	MCB	Camp Pendleton	
200	Site 45 Dry Cleaning Facility	29	MCRD	Parris Island	သွ
24	Removal Action at DRMO Manana Storage A	30	FISC	Pearl Harbor	Ī
52	PCB Transformer Filter Area Bldg 3009	31	Apra Harbor	Guam	Marianas Islands
533	Dialdrin Removal	32	FISC	Pearl Harbor	Ī
54	PCB Removal	32	FISC	Pearl Harbor	Ī
55	Sandblast Grit Stabilization	33	Hunters Point SYD	San Francisco	δ
29	Site 1 Northern Riverside Disposal	34	Allegany Ballistics Lab	Rocket Center	≩
57	Mercury Burial Vault Removal	35	PNSYD	Portsmouth	ME
80		35	PNSYD	Portsmouth	ME
50	Industrial Waste Treatment Plant Closure, Bld	35	PNSYD	Portsmouth	ME
8	Removal of USTs	36	Midway	Midway	NS
6		37	NAS Mare Island	Vallejo	Š
62	Site 11 Bida 866	38	NAS Mare Island	Vallejo	Ş
;					

Table C-1 Project Name and Location (Continued)

Project		Respondent			
_	Project Name	<u>0</u>	Base	City	State
£ 6	Tank Farm #5	20	NETC	Newport	굔
3	Tanks 53/56 Removal Action	20	NETC	Newport	굔
55		39	CNSYD	Charleston	သင
9	LIST Removals	40	NAS	Glenview	ے
67	Horizontal Recovery Well Pump and Treat	41	NSCS	Athens	ВĄ
89	Joint Small Arms Range	42	FT Polk	FT Polk	_
9	PSC 18 Golf Course Rubble Area	43	MCLB	Albany	Q
8		43	MCLB	Albany	∀
7	PSC (Carpenter Shop Wood Preservation Ta	43	MCLB	Albany	δA
72	Site Cleanup at Former Gas Station (Site 717	44	NTC	Orlando	7
73	Soil Remediation at NEX Gas Station	44	Naval Air Station	Meridian	MS
74	Biometric Pumping	44	NAS Whiting Field	Milton	긥
75	Site 1 Landfill	45	NAS	Pensacola	1
76	Biocomposting of Explosive Contaminated So	48	NSWC	Crane	Z
1		47	NAS Cecil Field	Jacksonville	교
78	MCB Hawaii Biopile	48	MCB Kaneohe	Kaneohe Bay	Ī
62		64	Hunters Point	Hunters Point	Š
8	Base Catalyzed Decomposition Process	20	Naval Station	Guam	Marianas Islands
2	Samos	51	Longhom Army AmmunitionKamack	Karnack	¥
82	Site 16 Landfill	51	Longhom Army AmmunitionKamack	Karnack	¥
83	Site 12 Landfill	51	Longhorn Army AmmunitionKarnack	Karnack	¥
84	Burning Ground #3	51	Longhom Army AmmunitionKarnack	Karnack	¥
28	Free Product Removal System	52	NAS North Island	Coronado	S
8	TCE Plume Remediation	53	Naval Air Station	Fort Worth	¥
87		54	Naval Station	San Diego	క
88	I	55	MCAS	Cherry Point	ပ္ရ
68		55	MCAS	Cherry Point	SC

Table C-1 Project Name and Location (Continued)

		To reduce 10 000 CY of soil to non-hazardous material		At conclusion of remediation contract, no further action	required, so there is no O&M cost.	ALL AND THE PARTY OF THE PARTY		Treatment system is operational and is controlling plume. O&M to continue until levels of TCE are below 5 ppb.			_andfill wastes must be excavated to eliminate contact with	nd capped.	Scope: remove 52 - 50,000 gal underground storage tanks	(USTs) and 10 - 2,000 gal USTs and contaminated soil.	Remove all distributed piping not paved over.	Site characterization with goal of natural attenuation. Former	nydrant system within 100 leet of public water well.	Need to contain plume and remediate site quickly as it is increased in a National Benister of Historic Places site	Newington Town Forest Pump and freatd for containment	only. 75% of the surface was capped.	Originally scoped as SVE. Changed to excavation because	of supposed high water table. Project is much more	expensive initially. No O&M costs following excavation.	
	Comments	To reduce 10.0		At conclusion c	required, so the	SII		Treatment syst O&M to continu			Landfill wastes	groundwater and capped	Scope: remov	(USTs) and 10	Remove all dis	Site characteri	nyorant system	Need to contai	Newington To	only. 75% of t	Originally scor	of supposed h	expensive initi	
	nollene lox-3	3				Uncharacterized landfills						Pesticides												
	9		0		0	1	0	0	0	0		-			0		2			0			0	0
Ments	%		1		0	0	0	0	0	0		0			0		2			_			0	0
Suoc	oaki selak	*	-		-	0	0	0	-	0		-		-	0		9			-			0	0
Stravios, court	SOUS THOMAS	5	7		0	0	0	-	-	-		~			0	•	0			~			-	-
	(1) (1) (1) (1) (1) (1) (1) (1) (1) (1)	3	0		_	0	-	0	0	0		-			-		0			_			-	0
	1080X	ر خ	0	,	7	80	6	5	11	12		13			14	!	15			16			12	18

Table C-2 Project Contaminant and Comments

																		-						ı			
	MINERAS	CO											Contract cost amount does not include investigation.	Very successful project, a model for other bases. Contract	cost amount does not include investigation.	Depth of contamination was greater than excavation	capability. Contract cost does not include investigation.	Significantly more contamination discovered than planned.		SVE system works fine, but resin vapor system (RVS)	innovative technology has caused several problems. RVS is	being used to treat the extracted vapors, instead of activated	carbon beds, but it doesn't work properly.				
	noitene lo	EX.				Methane gas/landfill waste			Low level radioactive waste						Refuse												
				0	0	-	0	0	-	0	0	0	0		1			0	0				0	0	0	0	0
Nents	80	2	0	0	0	0	1	0	0	0	0	0	0		0			0	0				0	1	0	0	0
Stravios chodie	Poster States	196	0	0	0	0	1	0	0	0	0	-	0		0			0	-				0	0	0	0	0
*	SOLOS TO SOLOS	5	1	-	0	-	0	0	0	1	1	0	1		0			0	0				-	0	0	0	0
	(H)	201	0	0	-	0	-	-	0	0	-	0	0		0			1	1				0	0	-	-	-
	29/0	600	19	20	21	22	23	24	25	56	27	28	29		30			31	32				33	34	35	36	37

Table C-2 Project Contaminant and Comments (Continued)

	Comments				Operation on the treatment system will not be continuous if	the contaminant is treated on a consistent level below the	WOL.						And the state of t	This is a pilot study.			and the set of the set			-	This project is a new technology demonstration. Material	recycled in asphalt mix.	Free Product (NAPL) is suspected in the ground water.		
	HOHRIERICH					-		447		lead				PAH's	Pesticides				Pesticide Dialdrin				Explosives		
			0	0		(>	0	0	-	0	0	0	-	-	0	0	0	1	0		0	1	0	0
Ments	SEST	0	0	-		•	2	0	0	0	0	-	0	-	0	0	0	1	0	1		0	0	0	1
Snot	Coste Stelen	0	0	-		(2	0	0	-	0	-	0	-	0	0	٠-	0	0	0		-	-	1	1
*	project in Hydrocki red 5 project of the project of the child wards project	0	0	-		•	-	0	0	-	0	0	-	-	0	-	0	0	0	0		0	1	0	1
	Tiens Tiens	-	1	-		•	5	-	-	-	-	-	0	-	0	0	0	0	0	0		0	0	0	1
	projec	38	39	40			41	42	43	44	45	46	47	48	49	20	51	25	53	54		22	26	25	28

Table C-2 Project Contaminant and Comments (Continued)

	Summents					Demonstration Project on Innovative Technology			Contract Type is SPORTENVDETCHASN (Base closure)			Army & Navy Joint Project		Institutional Controls & Long Term Monitoring							9 months for soil and 15 years for Ground Water (GW)	Technology Demonstration. Project didn't meet goals in the	reg. Permit, but only soils from on base were used allowing	less stringent environmental regulation considerations.		
	nother left.	Decidinal Chamicale	from Industrial Waste		Asbestos										Pesticides					INT, RDX, HMX (explosives)						
	Ο.	\top	-	0	-	0	0	0	0	0	0	0	0	0	-	0	0	0	0	1	0			0	0	0
Nents	SE		0	0	1	-	0	0	0	0	0	0	-	-	0	0	0	0	0	0	0			0	0	1
one of	Pare		c	0	-	0	0	0	0	0	0	-	0	0	0	0	0	0	-	0	0			0	-	0
*	OHOPA PHOHA	5		0	-	0	0	-	0	0	0	0	0	0	-	0	0	0	-	0	-			0	0	0
	OI OI	3	c	-	-	0	-	-	-	1	-	0	0	0	0	-	-	-	-	0	-			-	0	0
	The Hydrollowing Services of the Charles of the Cha	6	ğ	9	61	62	63	64	65	99	29	89	69	70	71	72	73	74	75	9/	77			78	79	80

Table C-2 Project Contaminant and Comments (Continued)

	STUBILIS									Team building/partnering was the most effective part of the	work in reducing cost and saving time.	Select monitored natural attenuation with hot spot	remediation of soil on a 40 acre landfill with residual soil and	GW contamination saved about \$4M in construction and over	\$10M in O&M costs
	HOHELE	Exple							MTBE						
	7	Office	0	0	0	0	0	0	1		0				0
Ments	4	ê Ş	0	0	0	0	0	0	0		0				0
Suo0	Pared S	No.	1	-	-	0	0	1	0		0				0
78	2010	OES	-	1	-	-	0	1	0		-				~-
		ING.	0	0	0	0	-	-	-		0				-
shows shope	- J	2014	84	82	83	84	82	98	87		88				88

Table C-2 Project Contaminant and Comments (Continued)

Applicable Cleanup Standards		36	popod gaysta	0	0 0	1 0		0 0		0	0 1	0 1	- 0	-	- 0		-		-	0 1				0 0	1 0
		100	Backer.	T			0 0		0 0	0 0	0 0	0 0	1 0		0 0	0 0	0 0			0 0		0 0	0 0	0	0 0
A	Pheter strang	har:	other .	1	0	0	0	0	1	0	1	1	0	1	1	0	0	1	0	0	-	1	0	0	0
Reason for Technology Selection	Shents	asau sau	MILITIMA	0	0	0	-	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0
	SHAMMAN	ما لاقر	No Hi	0	-	-	-	0	0	-	0	-	-	-	-	_	1	0	1	-	0	0	-	-	0
			Regular	-	0	0	1	0	-	-	-	-	~ -	-	0	0	-	0	1	0	0	-	0	0	0
			ways echedu	-	-	-	0	0	0	0	0	0	0	-	0	0	0	0	0	0	0	-	0	0	0
	80,	Meall	1500	0	-	_	0	-	-	-	-	-	-	_	0	0	-	0	0	-	0	0	0	0	1
		ତ ୍	CELLINA	0	0	0	0	0	0	0	0	0	-	_	-	0	0	0	0	-	0	0	0	0	0
		9	Project William Cost	5	9	7	&	6	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	5 6

Table C-3 Reason for Technology Selection and Applicable Cleanup Standards

ndards		91	1815 Y	redu	0	0	-	-	1	0	1	1	0	-		-	•	0	T	0	T	-	-	0	-	-
eanup Star			280	Bachs Risk Fe	_	-	0	0	0	-	0	0	0	0		•	0	F	o	T .	0	-	0	1	0	0
Applicable Cleanup Standards	Q.		v,			0 0	0 0	0 0	0	0 0	0 0	0 0		0 0	0 0	0 0	0 0	0 0			0 0	0 0	0 0	0	0 0	0 0
Ā	Diezell & Stuam	Insod*	•	N Jallo	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-	0	0	0	0	0	0
	Stuants	S.S.	No. Tr.	MILIM	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	-	0	0	0	0	0	0
	STUBILIS.	Redui			1	0	1	0	-	-	-	0	0	1	-	0	1	1	1	-	0	0	0	1	1	1
Selectio			OK	Regul	0	1	1	-	1	0	0	-	0	0	ŀ	1	0	1	0	0	0	1	1	1	0	0
or Technology Selection			3	Sche	0	0	0	0	0	1	0	0	0	0	1	0	1	0	1	1	0	0	0	0	0	0
for Tech		Pauce		1 500	-	-	1	1	ļ	-	0	0	0	Į	-	1	0	0		1	-	-	1	-	0	0
Reason			ত ব	TO THE PARTY OF TH	0	0	0	0	0	0	-	0	-	0	-	-	0	0	0	0	0	-	-	0	0	0
		A SULPA	9 ₄	29/014	27	28	53	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48

Table C-3 Reason for Technology Selection and Applicable Cleanup Standards (Continued)

ls		93	85	red oi	0	0	0		0	-	-	.	1	1	1		1	•	-	0	0	-	0	-	0	
andare		4	785	دوم																						
uup St		Ą	۳ اخ	aleka Tela	-	0	-	0	-	0	0	0	0	0	0	0	0	0	0	-	-	0	0	0	0	-
e Cleai			Ó	9,40	0	•	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-	0	0	0
Applicable Cleanup Standards	Que		٠,			0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-	0
A	Quezett stuant	amsodi	i.	othel	0	0	0	0	0	0	-	0	0	0	0	1	1	0	0	0	0	-	0	-	0	0
	SYV	· · · · · · · · · · · · · · · · · · ·		MILITUM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	-	-	0
	STUBILIS	Sedullo	OLION,	EHBCH		0	0	0	-	1	-	1	1	-	1	0	0	0	-	-	0	0	0	0	0	1
Reason for Technology Selection			Tox	Regula	0	0	1	0	0	1	0	-	1	1	1	0	0	1	1	0	0	0	-	0	0	0
nology S			7:	Scheor	0	0	1	0	-	-	0	0	0	0	0	0	0	0	0	-	-	0	0	0	0	0
for Tech		Pance	<u> </u>	1 600	-	0	0	1	0	0	0	0	0	0	0	0	0	0	-	-	0	0	0	0	-	0
Reason !		•	ે	Cerllin	0	1	0	0	0	0	-	0	0	0	0	0	0	-	-	0	0	0	0	0	0	0
			9.	Project William Cost	49	20	51	52	53	54	55	26	25	0	29	61	62	63	64	65	99	29	69	20	71	72

Table C-3 Reason for Technology Selection and Applicable Cleanup Standards (Continued)

ards		oner-	red of 3	0	0 .	- 1	0 ·	<u>.</u>	•	-	.	0	0	0	0	-		0	•	٥
nup Stand		•	8	-	1	0	1	0	0	0	Ψ.	-	-		1	0	0			-
Applicable Cleanup Standards		· ·	ONONORE		0	0	0	0	0			0	0	0	0	0	.	.	0	0
Appli	Ok Tek		740%	0	0	0	0	0	o 	0	o 	0	0	0	0	0	0	0	0	
	, e	ingodxi	other	0	-	0	0	0	-	0	-	0	0	0	0	0	0	0	0	0
	Diezelt e. Strame	SS	MINITIA	0	0	0	0	0	0	0	0	-	-	-	-	0	0	0	0	0
	Jemer	Aequi.	THECHIVE	0	0	0	0	-	0	0	0	-	-	-	1	-	1	1	1	0
election	Straman	ζ.	Redulator.	0	0	-	1	0	0	0	0	1	-	_	-	1	1	0	1	1
for Technology Selection			Schedule	0	0	0	0	-	0	0	0	0	0	0	0	0	0	0	0	0
for Tech		NA ³ IICO	1500	0	0	0	-	-	0	-	0	0	0	0	0	0	0	-	-	-
Reason		í	S ARHIM	-	0	0	0	0	0	0	-	0	0	0	0	0	0	0	0	0
			Project William Cost	73	74	75	9/	11	78	79	80	81	82	83	84	85	86	87	88	88

Table C-3 Reason for Technology Selection and Applicable Cleanup Standards (Continued)

		- 7					1						_		1			- 1	· T			-	_			_
mance thet ling lingles basessment ling project	Acceptable	Successful	Acceptable	Successful	Acceptable	Successful	Acceptable	Successful	Successful	Successful	Successful	Successful	Acceptable	Successful	Successful	Successful	Acceptable	Acceptable	Successful							
ince ince	-	2	7	က	ო	2	2	2	4	4	4	-	4	7	7	7	7	7	4	4	7	3	7	2	4	4
rtorma Weath Pundin	4	2	2	က	4	2	7	2	1	1	1	-	4	2	1	2	-	2	-	-	-	7	4	2	4	4
alahas ad Abo	4	7	7	က	4	7	7	2	4	4	4	4	4	2	2	2	5	2	4	4	4	2	4	2	4	4
Conditions Performance Conditions Performance Conditions Performed Politice Conditions Politice Politi	-	-	1	-	-	-	7	-	4	4	4	1	4	7	1	2	7	7	-	-	-	1	4	1	-	-
ie Cort	7	4	2	4	က	3	က	2	1	4	4	4	က	2	2	2	2	2	4	4	-	2	2	2	4	4
Contract Disputes Contamination Plants Contract Disputes Contaminas Plants Contamination Plants Contract Plant	4	3	က	2	က	2	က	2	7	7	2	2	3	2	2	2	2	7	-	2	4	2	4	7	2	2
2 2	-	4	က	4	4	2	2	2	4	4	4	4	4	2	7	7	2	2	4	4	4	7	7	2	4	4
8919110	-	-	-	-	~	-	-	-	-	-	-	-	က	7	-	7	7	2	-	-	-	-	1	-	-	1
Solling Sollin	4	-	3	-	-	2	2	7	7	-	-	-	3	-	-	-	-	-	-	-	2	-	-	-	-	1
Contract New Contract	2	2	-	-	7	2	2	2	4	4	4	4	4	2	-	2	7	7	4	4	4	7	2	7	4	4
THE THE	-	2	-	-	7	2	2	2	4	4	4	4	4	2	-	2	2	7	-	-	4	2	2	7	7	7
12.72	_	2	2	4	7	2	7	7	-	-	-	-	2	7	-	7	2	7	-	-	-	-	7	7	-	-
rial de	2	-	-	-	-	7	-	7	2	-	-	7	2	2	-	-	.2	7	-	-	-	-	2	7	-	2
neld Bulland Soc	2	-	-	-	-	2	-	6	2	-	-	2	က	-	-	-	-	2	-	-	-	-	-	7	-	7
600 VI	-	-	-	-		-	-	-	-	-	-	-	က	-	-	-	-	7	-	-	2	-	-	-	-	-
Jielu G	-	-		-	-	-			-	-	-	0	-	-	-	-	-	-	-	-	-	0	0	-	0	-
A de l'umes dos toles di tolos de	5	9	7	. ac	5	9 0	1-	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	စ္တ

Table C-4 Project Results

											-									<u>,</u>	_	_		-	- 1	_	_
Wernent ament	Alno Mical Imolves Assessing Political Assessing Political Imolves Assessing Political	Acceptable	Successful	Acceptable	Acceptable	Successful	Successful	Acceptable	Successful	Successful	Successful	Acceptable	Successful	Successful	Acceptable	Acceptable	Successful	Successful	Successful	Successful	Acceptable	Successful	Successful	Successful	Successful	Successful	Successful
و بیاره		4	7	4	4	4	4	2	4	7	7	1		4	4	4	2	7	4	7	7	-	-	က	3	4	က
Į,		4	-	1	2	2	1	1	-	2	1	1	2	-	2	က	2	7	2	2	7	7	3	7	3	4	1
	a Root	3	7	2	2	2	4	2	4	2	3	က	2	4	2	2	4	2	3	3	2	2	3	7	4	4	4
Eulmes,	Condition Per Anding Condition Severe Funding Politics	4	-	3	2	2	1	-	1	-	1	-	3	-	-	က	2	1	1	1	2	7	ŀ	l	-	1	1
ુ છું શુ	per Diepur Comunionay Paraction of the Control of t	3	2	2	2	2	2	2	22	2	2	4	4	4	2	2	4	2	4	3	2	7	3	4	2	4	4
LEULION	inaliding real dispurition of the Company of the Co	3	4		-	-	7	-	1	2	2	4	4	4	2	2	4	2	4	က	2	2	က	2	က	4	7
	- Z - Z	-	4	4	2	2	4	7	4	2	4	7	3	4	4	4	7	1	4	7	2	4	က	4	4	4	4
g _o		-	-	-	-	-	-	7	-	7	-	1	3	-	-	2	-	-	-	-	2	Ţ.	-	1	2	2	1
10 8 7.	ent Penaltiding ract Pauliding ream Contracto	4	-	-	-	-	-	-	4	7	-	2	-	4	2	-	-	-	2	-	2	-	4	4	4	4	1
Contr	ementack Incentification Contra	4	4	4	7	-	4	7	4	7	-	2	2	4	4	4	7	2	4	2	2	4	4	4	7	4	1
	THE TO	4	4	4	7	-	4	-	2	7	7	7	2	-	2	2	-	2	2	-	2	-	4	4	2	4	-
	1877 GE	4	-	-	-	-	-	-	-	7	-	-	2	-	7	3	-	-	-	-	2	-	-	-	က	2	-
	The delay	2	-	-	2	7	-	2	-	2	7	-	2	-	-	2	7	-	2	2	7	-	-	2	-	-	-
9	limeld Sampli	7	-	2	2	7	-	-	2	2	7	-	2	-	2	2	-	-	2	က	2	-	-	7	-	-	-
	05 No.	3	-	-	-	-		2	-	7	-	-	2	-	2	2	2	-	2	3	2	-	-	-	က	-	-
	le Ollar	-	-	0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	weld Annous Cooperate Olyoperate Colors	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	84	49	20	51	52	53	54	55	56

Table C-4 Project Results (Continued)

																		_							
mance thet ding involvement ding project passessment	Successful	Acceptable	Successful	Successful	Acceptable	Successful	Acceptable	Successful	Acceptable	Successful	Successful	Acceptable	Successful	Acceptable	Unsuccessful	Successful	Successful	Acceptable	Successful						
	7	7	7	4	4	4	က	1	7	က	ဗ	က	7	က	7	7	4	4	7	2	က	က	-	-	-
Condition Performance Conditions Sever Funding Politics Technology	2	7	2	-	1	1	2	2	7	*	2	4	4	4	7	7	4	-	7	2	က	7	1	1	1
ajanas d KBO	2	7	2	4	7	4	2	3	4	4	4	4	4	က	4	7	4	4	က	-	-	က	4	4	4
is coursel	-	7	1	-	က	1	2	7	-	-	-	7	-	-	က	-	-	က		-	-	-	-	-	1
performance contamination bear severe	7	7	2	4	က	2	2		က	4	4	4	4	7	က	7	4	4	4	4	4	3	4	4	4
aniemactor performance contract Disputes Co	2	က	2	4	4	4	2		2	4	7	4	3	က	က	4	4	4	4	4	2	3	4	4	4
Sol Tool	7	2	2	4	2	4	3	7	2	þ	4	3	7	4	4	4	4	4	2	4	4	4	4	4	4
Selling Troop	τ-	-	ŀ	ļ	3	2	1		2	3	1	ဗ	1	7	7	-	-	3	2	-	-	7	-	-	1
contract incertives in contract emails in contract incertives in contract in c	2	7	2	2	4	4	7	-	4	-	4	4	4	-	-	-	-	က	-	-	4	4	-	-	1
on Control	2	2	2	4	7	4	4	4	4	4	4	4	4	4	4	4	4	4	7	7	7	4	-	-	1
THE THE	-	7	_	4	4	4	4	1	1	4	1	4	4	4	4	4	7	-	7	7	7	4	-	-	1
SAY	-	7	-	-	3	2	က	-	-	2	2	က	-	-	-	τ-	7	-	-	7	-	7	-	-	1
eld Brill A de'l	1	2	7	-	2	-	-	-	-	-	7	7	က	-	-	7	-	7	7	7	-	-	-	-	1
oals mald it	-	7	2	-	2	-	-	-	-	-	2	2	3	-	-	7	-	7	-	-	-	-	-	-	1
neld Bullumes Solord Ul Dalord	, -	-	-	-	2	-	-	-	-	-	2	2	-	-	-	-	-	က	7	2	-	က	-	-	1
Ol Y. Berry	-	-	-	-	-	-	-	1	0	-	-	-	-	-	0	-	-	-	-	0	-	-	-	-	7-
prolec	22	28	29	99	63	64	65	99	29	68	69	70	71	72	73	74	75	9/	77	78	79	80	81	82	83

Table C-4 Project Results (Continued)

Table C-4 Project Results (Continued)

E (cost plus) O 7 Project complete	1000 C	adyl John Classicy of Soloto	1003 KJOSK	HEIMO	SINDINIS RUE	percent mplete	OSMICOST
E (cost plus) 0 3 Project complete	2	e (cost plus)	0	_		Project complete	0
Cost reimbursable (cost plus) 4518700 18 Design-build contract 76-99% Cost reimbursable (cost plus) 0 36 Design-build contract 76-99% 10 Cost reimbursable (cost plus) 7000000 18 Design-build contract 76-99% 10 Firm, fixed price (lump sum) 7000000 20 Design-build contract 76-99% 10 Cost reimbursable (cost plus) 680000 19 Separate contracts 76-99% 10 Cost reimbursable (cost plus) 6810000 24 Separate contract 76-99% 10 Cost reimbursable (cost plus) 2360000 18 Design-build contract 76-99% 10 Cost reimbursable (cost plus) 2360000 18 Design-build contract 76-99% 10 Cost reimbursable (cost plus) 2360000 24 Separate contracts 26-50% 26-50% Cost reimbursable (cost plus) 2360000 36 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 250000 36 Separate contracts	9 (4	Cost reimbursable (cost plus)	0	3		Project complete	0
Cost reimbursable (cost plus) 0 36 Design-build contract 76-99% Cost reimbursable (cost plus) 0 12 76-99% 10 Cost reimbursable (cost plus) 3000000 20 Design-build contract 76-99% 10 Firm, fixed price (lump sum) 3000000 20 Design-build contract 76-99% 10 Cost reimbursable (cost plus) 6680000 19 Separate contract 76-99% 10 Cost reimbursable (cost plus) 6910000 24 Separate contract Project complete 1 Cost reimbursable (cost plus) 1020000 18 Design-build contract 76-99% 2 Cost reimbursable (cost plus) 236000 9 Design-build contract 76-99% 2 Cost reimbursable (cost plus) 200000 24 Separate contracts 76-99% 2 Cost reimbursable (cost plus) 350000 30 Separate contracts 76-99% 2 Cost reimbursable (cost plus) 274000 6 In-house design & contracts 76-99% 1	7		4518700	18		Project complete	0
Cost reimbursable (cost plus) 0 12 76-99% 10 Firm, fixed price (lump sum) 7000000 18 Design-build contract 76-99% 10 Firm, fixed price (lump sum) 3000000 20 Design-build contract 76-99% 10 Cost reimbursable (cost plus) 6880000 19 Separate contract 76-99% 76-99% Cost reimbursable (cost plus) 1020000 18 Design-build contract 76-99% 76-99% Cost reimbursable (cost plus) 236000 9 Design-build contract 76-99% 76-99% Cost reimbursable (cost plus) 200000 24 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 200000 36 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 250000 36 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% 76-99% Cost reimbursable (cost plus) 1750000 3 Separate contracts <td>- α</td> <td>Cost reimbursable (cost plus)</td> <td>0</td> <td>36</td> <td></td> <td>%66-92</td> <td>0</td>	- α	Cost reimbursable (cost plus)	0	36		%66-92	0
Firm, fixed price (lump sum) 7000000 18 Design-build contract 76-99% 10 Firm, fixed price (lump sum) 3000000 20 Design-build contract 76-99% 10 Cost reimbursable (cost plus) 6680000 19 Separate contracts Project complete 1 Cost reimbursable (cost plus) 6910000 24 Reparate contract Project complete 1 Cost reimbursable (cost plus) 1020000 9 Design-build contract 76-99% 7 Cost reimbursable (cost plus) 200000 24 Separate contracts 26-50% 2 Cost reimbursable (cost plus) 200000 8 Design-build contract 76-99% 7 Cost reimbursable (cost plus) 350000 36 Separate contracts 76-99% 2 Cost reimbursable (cost plus) 350000 30 Separate contracts 76-99% 7 Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% 7 Cost reimbursable (cost plus) 274000 3 <	0	Cost reimbursable (cost plus)	0	12		%66-92	0
Firm, fixed price (lump sum) 3000000 20 Design-build contract 76-99% Cost reimbursable (cost plus) 6680000 19 Separate contracts Project complete 1 Cost reimbursable (cost plus) 6910000 24 Project complete Project complete 1 Cost reimbursable (cost plus) 1020000 18 Design-build contract Project complete 1 Cost reimbursable (cost plus) 2360000 24 Separate contracts 26-50% 2 Cost reimbursable (cost plus) 2360000 24 Separate contracts 26-50% 2 Cost reimbursable (cost plus) 200000 3 Separate contracts 26-50% 2 Cost reimbursable (cost plus) 250000 3 Separate contracts 26-50% 3 Cost reimbursable (cost plus) 250000 18 In-house design & construction 76-99% 3 Cost reimbursable (cost plus) 250000 18 In-house design & construction 76-99% 3 Firm, fixed price (lump sum) 1550000 3 S	6	Firm fixed price (lump sum)	7000000	18	Design-build contract	%66-92	1000000
Cost reimbursable (cost plus) 6680000 19 Separate contracts 76-99% Cost reimbursable (cost plus) 6910000 24 Project complete 1 Cost reimbursable (cost plus) 3100000 18 Design-build contract Project complete 8 Cost reimbursable (cost plus) 2360000 24 Separate contract 76-99% 76-99% Cost reimbursable (cost plus) 2360000 24 Separate contract 76-99% 76-99% Cost reimbursable (cost plus) 200000 24 Separate contracts 26-50% 26-50% Cost reimbursable (cost plus) 200000 36 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 250000 30 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 250000 18 In-house design & construction 76-99% 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% 76-99% Cost reimbursable (cost plus) 155000 3 Separate cont	+	Firm. fixed price (lump sum)	3000000	20	Design-build contract	76-99%	0
Cost reimbursable (cost plus) 6680000 19 Separate contracts Project complete Cost reimbursable (cost plus) 6910000 24 Project complete Time and materials 3100000 18 Design-build contract Project complete Cost reimbursable (cost plus) 2360000 24 Separate contracts 76-99% Cost reimbursable (cost plus) 2360000 24 Separate contracts 76-99% Cost reimbursable (cost plus) 200000 8 Design-build contract 76-99% Cost reimbursable (cost plus) 200000 36 Separate contracts 76-99% Cost reimbursable (cost plus) 250000 30 Separate contracts 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 250000 6 In-house design & construction 76-99% Cost reimbursable (cost plus) 175500 3 Design-build contracts 76-99% Cost reimbursable (cost plus) 1500000 3 Separate contracts 76-99%<	5		0	0	Design-build contract	76-99%	0
Cost reimbursable (cost plus) 6910000 24 Project complete Time and materials 3100000 18 Design-build contract Project complete Cost reimbursable (cost plus) 2360000 24 Separate contracts 76-99% Cost reimbursable (cost plus) 2000000 24 Separate contracts 26-50% Cost reimbursable (cost plus) 2000000 36 Separate contracts 76-99% Cost reimbursable (cost plus) 350000 36 Separate contracts 76-99% Cost reimbursable (cost plus) 250000 30 Separate contracts 76-99% Cost reimbursable (cost plus) 250000 6 in-house design & construction 76-99% Cost reimbursable (cost plus) 274000 18 in-house design & construction 76-99% Cost reimbursable (cost plus) 175500 3 Design-build contract 76-99% Cost reimbursable (cost plus) 1500000 6 in-house design & contracts 76-99% Cost reimbursable (cost plus) 1500000 3 Separate contracts 76-99%	1 6		0000899	19	Separate contracts	Project complete	150000
Time and materials 3100000 18 Project complete Project complete E Cost reimbursable (cost plus) 10200000 18 Design-build contract 76-99% 76-99% Cost reimbursable (cost plus) 2360000 24 Separate contracts 26-50% 26-50% Cost reimbursable (cost plus) 2000000 8 Design-build contract 76-99% 76-99% Cost reimbursable (cost plus) 250000 36 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 250000 6 In-house design & construction 76-99% 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% 76-99% Cost reimbursable (cost plus) 175500 8 In-house design & construction 76-99% 76-99% Cost reimbursable (cost plus) 1500000 3 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 1500000 3 Separate contracts 51-75% Cost reimbursable (cost plus) 938900	14		6910000	24		Project complete	0
Cost reimbursable (cost plus) 10200000 18 Design-build contract Project complete 8 Cost reimbursable (cost plus) 2360000 24 Separate contracts 26-50% 76-99% Cost reimbursable (cost plus) 500000 36 Separate contracts 26-50% 76-99% Cost reimbursable (cost plus) 2000000 36 Separate contracts 26-50% 76-99% Cost reimbursable (cost plus) 250000 30 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% 76-99% Cost reimbursable (cost plus) 1500000 3 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 150000 3 Separate contracts 76-99% 76-99% Cost reimbursable (cost plus) 800000 5 Separate contracts 51-75% Cost reimbursable (cost plus) 1020000 3	1,5		3100000	18		Project complete	0
Cost reimbursable (cost plus) 2360000 24 Design-build contracts 76-99% Cost reimbursable (cost plus) 800000 24 Separate contracts 26-50% Firm, fixed price (lump sum) 500000 36 Separate contracts 26-50% Cost reimbursable (cost plus) 350000 30 Separate contracts 76-99% Cost reimbursable (cost plus) 250000 20 Separate contracts 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 175500 3 Design-build contract 76-99% Cost reimbursable (cost plus) 150000 3 Separate contracts 76-99% Cost reimbursable (cost plus) 150000 3 Separate contracts 76-99% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 1020000 30 Design-build contract	2 4	Cost reimburgable (cost plus)	10200000	18	Design-build contract	Project complete	815500
Cost reimbursable (cost plus) 800000 24 Separate contracts 26-50% Firm, fixed price (lump sum) 500000 8 Design-build contract 76-99% Cost reimbursable (cost plus) 350000 36 Separate contracts 76-99% Cost reimbursable (cost plus) 250000 20 Separate contracts 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 175500 3 Design-build contract 76-99% Cost reimbursable (cost plus) 1500000 3 Separate contracts 76-99% Cost reimbursable (cost plus) 1500000 3 Separate contracts 51-75% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 1020000 30 Design-build contract Fright	2 5	Cost reimbursable (cost plus)	2360000	ဝ	Design-build contract	%66-92	0
Firm, fixed price (lump sum) 500000 8 Design-build contracts 76-99% Cost reimbursable (cost plus) 2000000 36 Separate contracts 76-99% Cost reimbursable (cost plus) 250000 20 Separate contracts 0-25% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 274000 3 Separate contracts 76-99% Cost reimbursable (cost plus) 150000 3 Separate contracts 76-99% Cost reimbursable (cost plus) 150000 3 Separate contracts 76-99% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 1020000 3 Design-build contract 51-75%	- 00		800000	24	Separate contracts	26-50%	260000
Cost reimbursable (cost plus) 2000000 36 Separate contracts 26-50% Cost reimbursable (cost plus) 350000 30 Separate contracts 76-99% Cost reimbursable (cost plus) 250000 6 In-house design & construction 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Firm, fixed price (lump sum) 175500 3 Design-build contract 76-99% Cost reimbursable (cost plus) 0 Separate contracts 76-99% 1 Cost reimbursable (cost plus) 150000 3 Separate contracts 0-25% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 1020000 30 Design-build contract 51-75%	9		200000	80	Design-build contract	%66-92	0
Cost reimbursable (cost plus) 350000 30 Separate contracts 76-99% Cost reimbursable (cost plus) 250000 20 Separate contracts 0-25% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Cost reimbursable (cost plus) 0 Separate contracts 76-99% 1 Cost reimbursable (cost plus) 150000 3 Separate contracts 0-25% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 1020000 30 Design-build contract 51-75%	2	Cost reimbursable (cost plus)	2000000	36	Separate contracts	26-50%	260000
Cost reimbursable (cost plus) 250000 20 Separate contracts 0-25% Cost reimbursable (cost plus) 274000 6 In-house design & construction 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Firm, fixed price (lump sum) 175500 3 Design-build contract 76-99% 1 Cost reimbursable (cost plus) 1500000 3 Separate contracts 76-99% 1 Cost reimbursable (cost plus) 1500000 3 Separate contracts 51-75% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 10200000 30 Design-build contract Fried complete	3 5	Cost reimbursable (cost plus)	350000		Separate contracts	%66-92	100000
Cost reimbursable (cost plus) 250000 6 In-house design & construction 76-99% Cost reimbursable (cost plus) 274000 18 In-house design & construction 76-99% Firm, fixed price (lump sum) 175500 3 Design-build contract Project complete Cost reimbursable (cost plus) 150000 3 Separate contracts 76-99% Cost reimbursable (cost plus) 800000 5 Separate contracts 51-75% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 1020000 30 Design-build contract Project complete	2		15000000		Separate contracts	0-25%	200000
Cost reimbursable (cost plus)27400018In-house design & construction76-99%Firm, fixed price (lump sum)1755003Design-build contractProject completeCost reimbursable (cost plus)0Separate contracts76-99%1Cost reimbursable (cost plus)15000003Separate contracts0-25%Cost reimbursable (cost plus)8000005Separate contracts51-75%Cost reimbursable (cost plus)93890072Design-build contract51-75%Cost reimbursable (cost plus)1020000030Design-build contractProject complete	23	Cost reimbursable (cost plus)	250000		In-house design & construction	%66-92	0
Firm, fixed price (lump sum)1755003Design-build contractProject completeCost reimbursable (cost plus)0Separate contracts76-99%1Cost reimbursable (cost plus)15000003Separate contracts0-25%Cost reimbursable (cost plus)8000005Separate contracts51-75%Cost reimbursable (cost plus)93890072Design-build contract51-75%Cost reimbursable (cost plus)1020000030Design-build contractProject complete	24	Cost reimbursable (cost plus)	274000	_	In-house design & construction	%66-92	0
Cost reimbursable (cost plus)0Separate contracts76-99%1Cost reimbursable (cost plus)15000003Separate contracts0-25%Cost reimbursable (cost plus)8000005Separate contracts51-75%Cost reimbursable (cost plus)93890072Design-build contract51-75%Cost reimbursable (cost plus)1020000030Design-build contractProject complete	25		175500		Design-build contract	Project complete	0
Cost reimbursable (cost plus)15000003Separate contracts0-25%Cost reimbursable (cost plus)8000005Separate contracts51-75%Cost reimbursable (cost plus)93890072Design-build contract51-75%Cost reimbursable (cost plus)1020000030Design-build contractProject complete	2 8		0		Separate contracts	76-99%	150000
Cost reimbursable (cost plus) 800000 5 Separate contracts 51-75% Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 10200000 30 Design-build contract Project complete	27		1500000	_	Separate contracts	0-25%	0
Cost reimbursable (cost plus) 938900 72 Design-build contract 51-75% Cost reimbursable (cost plus) 10200000 30 Design-build contract Project complete	280		80000		Separate contracts	51-75%	0
Cost reimhursable (cost plus) 10200000 30 Design-build contract Project complete	200		938900		Design-build contract	51-75%	
	2 6		1020000		Design-build contract	Project complete	276000

Table C-5 Contract Type and Cost

1500 M80	0	0 0			25000	0000	240000	000000	30000	1000		00001	00000/	0	0	30000	400000	0	0	5000	0	0	0	0	0	4000000	
	Project complete	51-75%	0,56-0/	0-25%	51-75%	76-99%	76-99%	20.000	0/88-0/	10-93%	51-/5%	Project complete	%66-92	Project complete	%66-92	51-75%	%66-92	Project complete	Project complete	0-25%	Project complete	76-99%	Project complete	\top	1	26-50%	2000
oluduage le	ssign-build contract		Design-build contract						Design-build contract	Separate contracts	In-house design & construction	Separate contracts	Design-build contract	Separate contracts	Decion-build contract	Coparate contracts	Separate contracts	Decise build contract	Design build contract	Coorate contracts	Separate contracts	In house design & construction	III-IIOuse design & construction	Deparate Contracts	In-house design a constraint	\neg	Separate contracts
May Tool Roy	28	517000 0	6300000 8	3500000 24	2500000 10	450000 24	400000 16	1000000	800000 7	18000000 36	09 000006	400000 2		L	\perp					9100000		\perp					7000000 360
adk) Joeth Ol to alor	e (cost plus)	e (cost plus)		-	+	-	sable (cost plus)	_		13	sable (cost plus)	dian (lumb cum)	rice (lumb sum)	Sable (cost pins)	+	sable (cost plus)	\dashv	_	rsable (cost plus)	+	rsable (cost plus)	rsable (cost plus)	\dashv	Cost reimbursable (cost plus)	Firm, fixed price (lump sum)	Cost reimbursable (cost plus)	Cost reimbursable (cost plus)
WAS OF CALL	6	20 00	1			Co	1	T	3 6	60	2	*	42	43	44	45	46	47	48	49	20	51	25	53	54	55	26

Table C-5 Contract Type and Cost (Continued)

TSOO WASO	5	0	0	2000000		100000	200000	0	0	75000				1000	0		80000	00009	210000	0	10000				30000		200000	0	
percent complete	Project complete	Project complete	Project complete	Project complete	0-25%	Project complete	Project complete	0-25%	Project complete	76-99%	Designation politicate	Project complete	Project complete	Project complete	%66-92	Project complete	%66-92	%66-92	0.25%	0-25%	76-99%	Designat complet	Project complete	Project complete	Project complete	Project complete	51-75%	%66-92	
amonus au	house design & construction			15		Congrate contracts	Separate contracts	construction		Design-build collulact	Separate contracts	Separate contracts	Separate contracts	Separate contracts	Senarate contracts	Separate contracts	Congrete contracts	Separate contracts	Separate contracts	Separate contracts	Separate contracts	Separate contracts	In-house design & construction	Design-build contract	Separate contracts	Γ	T		Design-pand contract
JIRING	-	75000	1	Ĺ	2000000				2/00000 48			3000000 27	60000		\downarrow		\perp				3,		150000 16	700000 24	1700000 60	500000 12			5000000 18
COST			1	- `	+	(snic	$\frac{1}{2}$	_	+		_	_		+	2		_		_	_	7	_			17	+	+	+	_
adkl vente (11 vale	3	Cost reimbursable (cost pius)	Firm, fixed price (lump sum)	Cost reimbursable (cost plus)	Firm, fixed price (lump sum)	Unit price	Cost reimbursable (cost plus)	Cost reimbursable (cost plus)	Cost reimbursable (cost plus)	COST Tellinguistics (cost	Cost reimbulsable (cost plus)	Cost reimbursable (cost pius)	Firm, fixed price (lump sum)	Cost reimbursable (cost plus)		Cost reimbursable (cost plus)		1.1:	Olin pilice	COSt telling	Cost reimb	Firm, fixed	Firm fixed price (lump sum)						
Tage of the same o	200	57	28	59	09	61	63	64	65	99	67	9	8	69	2	71	72	73	74	75	9/	11	78	2 6	2	8	<u>ھ</u>	82	Ca

Table C-5 Contract Type and Cost (Continued)

Table C-5 Contract Type and Cost (Continued)

				-	\neg		(e.	<u>e</u>	<u>e</u>	<u>ē</u>	<u>ē</u>					(e)					ore)	(e)			ore)				ļ
ı	en e						Increased (5% or more)	Increased (5% or more)	Increased (5% or more)	Increased (5% or more)	Increased (5% or more)	9	9	9	a	Increased (5% or more)	<u>e</u>	Je	er.	je Je	Increased (5% or more)	Reduces (5% or more)	ge	ge	Increased (5% or more)	ge	ge	ige	
	Burne	5	2005	No change	No change	No change	Increased	Increased	Increased	Increased	Increased	No change	No change	No change	No change	Increased	No change	No change	No change	No change	Increase		No change	一	Increase	No change	No change	No change	
				r more)		or more)	or more)					% or more)				or more)					or more)	Ahead of schedule (2% or more)	Ahead of schedule (2% or more)	6 or more)					
BOURING	erori			Ahead of schedule (2% or more)	e	Behind schedule (2% or more)	Dellilly Schodule (2% or more)	al al	9	<u>e</u>	le	Abead of schedule (2% or more)	al	ا و	2 0	Oli sciledule	ollicours (F.S.	الم الم	911	alile	Behind schedule (2% or more)	schedule (schedule (Behind schedule (2% or more)	4116	dile elile	dule	dille	ָ בַּבְּי
3	Coms,	Jally 16	Sollo	A hoad of S	On schedule	Bahind sch	Delillid sol	Selling schedule	On schedule	On schedule	On schedule	Ahead of	On schedule	on schodule	On schedule	Oil sciled	De schedule	On schedule	oli schodula	On schedule	Behind St	Ahead of	Ahead of	Behind S	On schedule	On schedule	On schedule	On schedule	250 = 5
		پر	1806°16	22			0	5		2,	3		0		3	3	C S	62	3 8	9 40	C) c					5 6	2 6	3 0	2
					(aloue)		1	r more)	L IIIOIE)				or more)			ľ	or more)				or more)	Or more	Under budget (2% of fillole)	Under budget (2% or more)	Under budget (2% or more)				
	BJUER	Ė			Over budget (2% of more)			Over budget (2% or more)	Over budget (2% or more)			الله الله	Under budget (2% or more)		*	*	Over budget (2% or more)	100	es	et	Over budget (2% or more)	Over budget (2% of more)	rager (27)	ndget (27	ndget (2%	et	jet	Jet	į
		Q,	30,50	2	ver budg	On budget	On pudget	ver bud	yer bud		on padder	On pudget	Juder bud	On pudget	On budget	On budget	Over bud	On budget	On budget	On budget	Over buc	Over buc	Onder D	Under bi	Under b	On pudget	On budget	On pagget	10000
			7	6	0	0	0	0	0			0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	_
			A.	i	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4
		-	C	X .	0	0	-	-	0	0	0	0	0	0	0	0	0	0	-	0	0	0	0	0	-	0	0	0	1
		(ر کرچ	30	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-	1
			J. 108.	600	5	g	7	. @	6	10	17	12	13	14	7	2	7 2	- 2	19	20	21	22	23	24	25	56	27	28	

Table C-6 Contract Funding and Performance

	90	Chang	ad	Increased (5% or more)	Increased (5% or more)	Reduces (5% or more)	Increased (5% or more)	Increased (5% or more)	Reduces (5% or more)	Increased (5% or more)	Increased (5% or more)	No change	No change	Increased (5% or more)	Increased (5% or more)	No change	Increased (5% or more)	Increased (5% or more)	No change	No change	Increased (5% or more)	Increased (5% or more)	Increased (5% or more)	Reduces (5% or more)	Increased (5% or more)	ncreased (5% or more)	Increased (5% or more)	Increased (5% or more)	
870	, empos	lie.		chadule (2% or more)	\top			On schedule Incr		edule (2% or more)					Oli scriedule		Oil scriedule	dule (2% or more)	(e)	-			dule (2% or more)		dule (2% or more)			Jule (2% or more)	
	ì	A NS NO.	wads T	ola	5	0	8	T	3 5	2 4	T	20 00			T		2	0	15	2 8		T	08	3 8	8 0	>	- 0	2 0	,
		ALEUMO,	er pen	200	Under budget (2% or more)	Over budget (2% or more)	Under budget (2% or more)	On budget	On budget	Under budget (2% or more)	On budget	Over budget (2% or more)	On budget	On budget	Over budget (2% or more)	Over budget (2% or more)	On budget	Over budget (2% or more)	Over budget (2% or more)	Under budget (2% of more)	On budget	On budget	On buaget	Over budget (2% or more)	Under budget (2% or more)	Over budget (2% or more)	Over budget (2% or more)	Over budget (2% of fillole)	Over budget (2% of fillole)
			79.5	10	0	0	0	0			\neg	0	0	0	0	0	0		-	-	-	0	0	\dashv	0	0	1	0	0
			d	NO.	0	0	0	-	0	0	-	0	0	0	1	0	0	0	1	1	0	1	0	0	1	0	1	-	0
			ې	8	0	0	0	0	0	1	0	1	1	1	0	1	1	-	0	0	-	0	0	0	0	0	0	0	0
			0,70	9010	30 1	3 2	32	-	34	-	36	37	-	39	40	41	42	44	45	46	47	48	49	20	51	52	53	54	55

Table C-6 Contract Funding and Performance (Continued)

			re)		1			(a)(0)	(0.00	(200	(2)		T		more)	more)	more)		more	more)	more)	more)	more)	()				
	OFUEUE	, ados	Reduces (5% or more)	No change	No change	No change	No change	Increased (5% of more)	No change	Increased (5% of more)	Increased (5% of more)	No change	No change	No change	Increased (5% or more)	Increased (5% or more)	Increased (5% or more)	No change	No change	-r	_	\neg	Increased (3% of more)	Increased (5% of increased	No change	No change	No change	
BUCB	outobac koms			On schedule			T	1		T	1	T		1	T		T	Ť		12 Behind schedule (2% or more)		0 Behind schedule (2% or more)	30 Behind schedule (2% or more)	Π		T		
		903	<u>0</u>	6 6		\perp	1	-	-	+	<u> </u>	45	2 5	2 9	-	1			1	-	-	-	-	-	-			
	BOULE	Perform	150	Under budget (2% or more)	On budget	Under budget (2% or more)	On budget	Over budget (2% of fillore)	Over budget (2 % of more)	Over budget (2% of more)	Over budget (2% of files	On budget	On budget	On budget	On budget	Over budget (2% of mole)	Under budget (2% or more)	Over budget (2 % of more	Under budget (2 % of more)	On budget	Over budget (2 70 of mis	On budget	Over budget (2.70 or min	On budget	Over budget (2 % of tilots)	On budget	On budget	On punger
		•		7	0							0	0	0	0	0	0	0	0	0	0		0		0	0	0	-
			ARIC	0	-	-	0	-		0	0	-	0	0	0	0	0	-	-	-	-	0	-	0	0	0	1	0
			g	0		0	0	0	0	0	0	0	0	-	-	-	0	0	0	-		0		0	-	-		0
		9	JAR S	2		0	-	0	0	-	-	0	+	-	+	+	-	0	0	0	0	1	9	9	0	-		-
			300	2	3 5	5 6	8	8	64	65	99	67	a a	8 8	8 8	7	72	73	74	75	76	77	2	79	8	8	82	83

Table C-6 Contract Funding and Performance (Continued)

			_	Ţ	Τ	Τ	٦	
Stuguty BAO'S	No change	No change	Increased (5% or more)	No change	Dedicor (6% or more)	Reduces (3% of Illoid)	Reduces (5% or more)	
CHEMOTA SUNTE TO MAGE!	On schodule			T	Behind schedule (2% of more)	Behind schedule (2% or more)	1	1
ds. Superformance	5	On budget	On budget	Over budget (2% or more) 40	On hildret	25 hindred (7% or more) 25		Onder budget (270 of mole)
1	0 10 110	0 0	0 0	0		- 6	0	ا ا
	<u> </u>			-		3	_	_
0,13	94 Mg	0	-	0 4	- •	0	0	0
45	010	84	30	8 8	8	87	88	58

Table C-6 Contract Funding and Performance (Continued)

			Water Table Depth Site Reuse	Site Reuse
Orginal ID	Contaminati	on Depth Extent Of Plume	11-20 feet	In 1-3 years
2001	21-30		21-30 feet	In 1-3 years
2	11-20 feet		11-20 feet	In 1-3 years
0 1		is completely on site	21-30 feet	In 1-3 years
~ a	11-20 feet		21-30 feet	In 1-3 years
σ	21-30 feet	anii vironose estre	Over 50 feet	In 1-3 years
9	Over 50 feet	extends beyong the property mis		In 1-3 years
= =====================================	31-40 feet	4th connectivities	Over 50 feet	In 1-3 years
12	Over 50 feet	extends beyond the property miss	0-10 feet	No definite plans (or no information)
13	11-20 feet	is completely oil site	0-10 feet	In 1-3 years
14	11-20 feet	is completely un site	0-10 feet	In 1-3 years
15	21-30 feet	is completely our suc	0-10 feet	No definite plans (or no information)
9	21-30 feet	extends beyond tile property	0-10 feet	No definite plans (or no information)
2 2	0-10 feet	is completely on site	11-20 feet	In 1-3 years
2	21-30 feet	extends beyond the property line	-	In 1-3 years
5 6	21-30 feet	extends beyond the property line	-	In 1-3 years
2 2	31-40 feet	extends beyong the property line	-	In 1-3 years
3 2	-	is completely on site	11-20 feet	In 1-3 years
3	+-		0-10 feet	In 4-10 years
23 62	-	is completely on site	0-10 feet	In 1-3 years
24		is completely on site	21-30 feet	No definite plans (or no information)
25	-	ing spaces of the	-	In 1-3 years
28	-	extends beyond the property min	-	In 1-3 years
27	-	is completely on site	21-30 feet	No definite plans (or no information)
28	0-10 feet			In 1-3 years
29	Over 50 feet			No definite plans (or no information)
တ္တ	Over 50 feet			In 4-10 years
31	21-30 feet		11-20 feet	In 1-3 years
32	0-1	in a property lin	over 50 feet	No definite plans (or no information)
33	Ove	extends beyond the property	-	No definite plans (or no information)
34	0-10 feet			

Table C-7 Extent of Contamination

th.	on Depth Extent Of Plume Wa	epth	Site Reuse
		11-20 feet	No definite plans (of no information)
3000	is sompletely on site	11-20 feet	No definite plans (or no information)
2	and the second second	11-20 feet	In 1-3 years
		Over 50 feet	In 1-3 years
ie com	is completely on site	0-10 feet	In 1-3 years
extends	extends beyond the property line	11-20 feet	No definite plans (or no intollitation)
has an	has an unknown extent	Over 50 feet	In 4-10 years
is comp	is completely on site	11-20 feet	In 1-3 years
		11-20 feet	No definite plans (or no information)
IS COM	is completely oil site	0-10 feet	No definite plans (or no information)
IIS COM	is completely on site	0-10 feet	In 1-3 years
200	ls compound on extent	0-10 feet	In 1-3 years
in com	is completely on site	21-30 feet	In 4-10 years
1100	pletely on one	0-10 feet	No definite plans (or no information)
	ofice on siles	0-10 feet	No definite plans (or no information)
IS COM	is completely on suc	Over 50 feet	In 1-3 years
		0-10 feet	No definite plans (or no information)
		21-30 feet	In 1-3 years
-		0-10 feet	In 1-3 years
-		0-10 feet	In 4-10 years
100 6	site on site	0-10 feet	No definite plans (or no information)
3	Indicated an energy	11-20 feet	In 4-10 years
100	sade heyand the property line	11-20 feet	In 4-10 years
exien	de beyond the property	11-20 feet	No definite plans (or no information)
	of on whole	0-10 feet	In 1-3 years
IS CO	is completely on site	21-30 feet	No definite plans (or no information)
15 CO	is completely on site	11-20 feet	
	otio conferen	11-20 feet	No definite plans (or no information)
IS C	is completely on site	11-20 feet	No definite plans (or no information)
CYIL	Silles Boyons and Spills	(bollaitas 2) = sit	

Table C-7 Extent of Contamination (Continued)

Site Reuse	In 1-3 years	In 1-3 years	No definite plans (or no information)	No definite plans (or no information)	In 1-3 years	No definite plans (or no information)	No definite plans (or no information)	In 4-10 years	In 1-3 years	No definite plans (or no information)		No definite plans (or no information)	In 4-10 years	No definite plans (or no information)	In 4-10 years	In 1-3 years	No definite plans (or no information)	In 1-3 years	In 1-3 years	No definite plans (or no information)	No definite plans (or no information)	No definite plans (or no information)				
Water Table Depth Site Reuse	0-10 feet	Over 50 feet	11-20 feet		21-30 feet	41-50 feet	21-30 feet	11-20 feet	0-10 feet	Over 50 feet	0-10 feet	11-20 feet	0-10 feet	0-10 feet		11-20 feet	21-30 feet	0-10 feet	41-50 feet	11-20 feet	11-20 feet	11-20 feet		\ <u></u>	11-20 feet	
		is completely on site		extends beyond the property little				anii yhaacaa ada baa	extends beyond the property	is completely oil site				is completely on site				is completely on site	is completely on site	010000	is completely on site	is completely un site	is completely on site	extends beyond the property min	is completely on site	is completely oil site
	Project ID Contamination Depth	0-10 feet	11-20 feet	21-30 feet	0-10 feet	0-10 feet	31-40 feet	11-20 feet	11-20 feet	0-10 feet	Over 50 feet	31-40 feet	0-10 feet	31-40 feet	0-10 feet	0-10 feet	11-20 feet	0-10 feet	21-30 feet	21-30 feet	11-20 feet	11-20 feet	21-30 feet	11-20 feet	Over 50 feet	11-20 feet
	Project ID	65	99	67	99	69	2	71	72	73	74	75	76	11	78	62	8	26	82	83	8	85	98	87	88	88

Table C-7 Extent of Contamination (Continued)

notherneldy is	The state of the s				Tanks recycled						Site characterization					Dual Phase Extraction			Pipe removal					Gravity Separation/Soil Washing		
	1	0	0	0	1	0	0	0	0	0	-	0	0	0	0	1	0	0	1	0	0	0	0	-	0	0
Teary Mall Treat	0	0	0	0	0	1	0	0	0	0	0	1	0	+	0	0	0	0	0	1	0	0	0	0	0	0
	1	0	0	0	0	0	0	0	0	0	0	0	0	0	,	0	0	0	0	0	0	0	0	0	0	0
8%	1_	0	0	-	0	0	0	0	-	0	0	-	0	0	0	0	0	. 1	0	0	0	0	0	0	0	-
SOG LIVE	0	0	0	0	0	0	0	0	0	0	0	0	-	0	0	0	0	0	0	0	0	0	0	0	0	0
WesodsId Britisod	-	-	0	0	-	0	-	0	-	-	0	0	-	0	0	0	0	0	-	0	-	0	-	0	0	-
Eo	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1 2	i	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
TOWN TOWN TOWN TO THE TANK TO	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-	0	0	0	0	0	0	0	-	0
COLUMBIA GAROLE	0	0	0	0	0	0	0	0	0	0	0	-	0	0	0	0	0	0	0	0	0	-	0	0	0	0
8 6 00 W	0	0	-	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
TOWN WAS THE OF THE WASHOND TO THE W	0	0	-	0	0	0	0	-	0	0	0	-	0	0	0	0	0	0	0	0	0	0	0	0	1	0
O. Indeed			+	-	-		-	,		-		O	+	-		-	-	-	-	-	-	0	0	-	0	-
Salora	. 2	9	7	8	6	10	1	12	13	4	15	16	17	18	19	20	21	22	23	24	25	56	27	28	59	30

Table C-8 Regulatory Goals and Remediation Technology

The state of the s	0 1 0 0 0 0 0 1	0 0 1 0 0 0 0	0	0 0 0 1 0 0 0 0 0	0 0 0 0 1 0 0 0 0	1 0 0 0 0 0 0 0 0 0	0 0 0 0 1 0 0 0 0	0 1 0 0 0 0 0 0 0 0	0 0 0 0 1 0 0 0 0	0 0 0 0 0 1 Armor stone revetment	0 0 0 0 0 0 1 0	0 0 0 0 0 0 0 1 Recycle for paving	0 0 0 0 0 0 0	0 0 0 1 1 0 0 0 0	0 0 0 0 0 0 0 0 1 Treatment or Bio-Slum	1	0 0 0 0 0 0 1 0	0 0 0 0 0 0 0 0 0	Excavation, fixation & recycled as	0 0 0 0 0 0 0	0 0 0 0		
STATE OF STA	0	0								_	0	0	\dashv	_	0	0	0	0			0		0
1805 No. 1905 No. 190	0 0	0	1	0 0		0 0	0			0	-	-	-	0	0	0	0 0	1 1			0		+
Haberta Steon House Was lord The British and House Was lord	31	32 1	33 0	34 1	35 1	36 1	37 1	38	39 1	40	41	42 1	43 1	44	45 1	46 1	47 1	48 1	49	50 1	51 1	52 1	53

Table C-8 Regulatory Goals and Remediation Technology (Continued)

	Holleng Transitor		Recycled to make asphalt			Triple Rinsing of Process Tanks	and Hand Cleaning		RCRA Subtitle C Cap	In Situ Thermal Desorption	Monitoring					Physical Separation / Chemical	Leaching		Low Permeability Subsurface	Membrane Liner					Monitoring w/GW extraction /	inteception		
	Y 0,	┰	-	0	0		-	0	0	-	-	0	0	0	0		-	0		-	0	0	0	0	_	-	0	
	day Jano dund	0	0	-	0		0	0	0	0	0	-	0	0	-		0	0		0	0	0	-	0	_	0	0	
	-6.	1	0	0	0		0	0	0	0	0	0	0	0	0		0	0		0	0	0	0	0	_	0	0	
	6 1/4	_	0	0	0		0	0	1	0	0	0	0	0	0		0	0		0	0	0	0	0		0	0	
	Disposition of Dispos	0	0	0	0	,	0	0	0	0	0	0	0	0	0		0	0		0	0	-	0	c		0	0	
	Reorge Onligor	-	. 0	0	, -	+	0	-	0	0	0	0	0	-	c	,	0	-		-	-	0	0	c	,	0	0	
	E C		,	, c	0	>	0	0	0	0	0	0	-	0	6	,	0	c	,	0	C	o	0	C		0	-	
	_ 0	- 1) c	0		-	0	0	0	0	0	-	c	c	-	>	c	0	,	c	c	c	0	٥	2	0	0	
	On Station of Colors of Co	.) c	> 0	0	-	0	0	0	0	- -	0	c	, c	, ,	>		0	>	c	0	0	0	,	-	c	•	,
9	Control of the Contro			> 0)	D	c	0	0	-	, -	- c	0	0	> 0	5			>	c	0				>	c	0	,
	THE SECTION OF THE SE)) >)		, -	- c	,	0	0	> 0	0	5 0	5			-	•	0	0	0		-	c	0	,
	SO TO TO	2	5	-))	0		,	-	0)	-	c	9	5		0	> 0	> -	- 6	2	c	>	۱,
	TOWN THE WAY SHOO TO WE WANTED TO THE WAY TO WORK TO THE WAY TO WE WANT TO WE WAY TO W	رم: مود د	54		56 1	57 1	7	- 1	- 6		70	2			I	0 29		29	L 69	,	2	\	1	ر د د	74 1	i	ري ع	2

Table C-8 Regulatory Goals and Remediation Technology (Continued)

	TO HOUSE JET HOUSE TO SOLO		ion topas	8	olle parion for the property of the parion for the	کي لاي	v	(e)	Cap ament Wand Tree Cap Carlo Dump Expla	Y	Teph Hallallon
١	1		0	c	-	0		0	0	\neg	Natural Attenuation for GVV
2 0		-		0	c	0	0	0	0	1	Biopile (exsitu)
3	2	+	+		,						Recycle Grit as raw material for
					_	0	0	0	0	_	ashpalt
5	2		+	>	,						Base Catalyzed Decompostion
					c	0	0	0	0	-	Process
+	+			, c	-	0	0	0	0	0	
+			0 0	,	· c	0	-	0	-	0	
5	_		0	, c	,	0	-	0	0	0	
)	+) c	,	-	0	0	0	-	0	
5 0	+) -	, c	0	0	0	0	0	-	Free-Product Pumping & Kemoval
	0 0	-	0	0	0	0	0	0	1	0	
5) c	- c	, c	0	0	0	0	0	0	0	
)) c	0		0	0	0	0	0	0	
-	-	>	,	•							Monitored Natural Attenuation for
			0	0	0	0	0	0	0	-	GW

Table C-8 Regulatory Goals and Remediation Technology (Continued)

1	seology (Geology Classification	F				 		
		(SIIOS BIAN	(81102.9)	Oldro	* Openock				in the second
		Impermea	radi loem	Permeable		¥.		,	Adm To Mouno 18
OL TOBIO	Tero Mor	Annay Walvistay (200 200)	Wavirelay Relay	Hos manay mi Kanikasa (e)		My Mounos	3510	OSNOS	DISSON BY FIEB PRODUC
5	-	0	0	0					
9	0	-	0	0	-	0	0	,	+
7	0	-	0	0		- 1		_	-
80	-	0	0	0	-	0			
6	0	-	0	0	-)		,	
9 0	-	1	0	0	0	, , , , ,	<u> </u>	-	0
=	0	-	0	0	•) 0		1	
12	-	-	0	0	τ-)		-	0
1 5	1	1	0	1	+	·		-	0
14	0		0	0	+	-		-	
15	0	-	0	0	-	-	0	-	
18	-	-	0	1	-	_	0	-	_
11	0	1	0	0	.	1	0	-	0
18	-	0	0	0	-	-	0	- 0	
19	-	0	0	0	0) > 0	0	-
20	-	0	0	0	0	,))	5	
21	-	0	0	0)	٥	-
22	-	0	0	0	-	0	0	o	
23	-	-	0	0	_	-	0	0	
24	-	0	0	0	-	-	0	-	>
25	-	0	0	0	.	o •) > c	-	
			•	•	•			_	

Table C-9 Site Geology

Nos alde anna de anna	, os ex
•	E
	₹2
	-
-	\rightarrow
1	+
-	
	Н
ĺ	-
- 1	
	-+
- 1	-+
ı	
1	$\neg \neg$
- 1	$\neg \neg$
	1
- 1	\neg
	1 1

Table C-9 Site Geology (Continued)

	Geology	Geology Classification			ַ כַּלַוּ וּמִּוּ	COLITAINIMI I I I I I I I I I I I I I I I I I			Glodildwater allected
		(Silos alde	(81105 81	eldes	*JONDAY				jak
		Imperme	had lavel	e de meable	YOO'N W			9	JOHN TO MOUNOIS
Orolect ID	Kely Jugh	lelli sandiya imi Kibines koo j	S Relatively	oldennado permado	Hose manage with the soll of t	IN MANAGED STATES	(SIO	Pomos	Olsson eree production
49	0	1	0	0	_	0			
20	0	1	0	0	-	-		-	0
51	-	0	0	0	_	0			
52	0	1	0	0	-				
53	-	0	0	0	-	0	_		
54	-	0	0	0		0 0	_		
55	0	-	0	0	τ.	0			
56	-	0	0	0	-	0	_	-	
57	0	1	-	0	-	0	_		
28	0	-	-	0	•	- -		-	0
29	0	1	1	0	_	0	-		
9	0	-	0	0	,	D	-	-	-
61	-	0	0	0	•			-	D
62	-	0	0	0	-	0	0		
63	1	1	-	-	-		(-	
64	1	1	-	-	_) 0 :	-	-
65	-	0	0	0	-		0	-	0
99	-	0	0	0	+)	0		
29	-	0	0	-	-		0	-	0
89	1	0	0	0	•		 -		
69	τ-	0	0	0	•	0	9		
70	-	٥	C	_	•		0		

Table C-9 Site Geology (Continued)

	Geology	Geology Classification	5)				
			(51105 5	910	Xo X				•
		(Impermed)	They loan	Ne Surregule	Asork.	200 No. 40 40 0			ANN THE MOUNDING
Orolect ID	Reis Mels	Om Claysill's sandigi and the compart of the compart of the control of the contro	Relatively	om of the spiral	Hos anamad Wallelay (a)	Pare Worldoop		ni baylossiq	DISSON BY THE PROMICE TO
71	-	0	0	0	,	980.41.02	0		
72	0	-	0	0	.	+	0	-	-
73	-	0	0	0	.	-	0	1	-
74	0	-	0	0	•	0	0		
75	0	-	0	0	0	1	o	-	0
76	0	-	0	0	-	0	0		
77	0	-	0	0	-	-	0	Ψ-	0
78	0	1	0	0	_	0	0		
79	0	-	0	0	-	0	0		
80	0	-	0	0	,	0	0		
81	1	0	0	0	-	0	0		
82	-	0	0	0	.	T	0	1	0
83	-	0	0	0	-	0	0		
84	-	0	0	0	-	1	0	-	0
85	0	-	0	0	•	1	0	-	-
98	-	-	1	0	-	-	0	-	-
87	-	-	0	0	-	•	0	-	-
88	0	-	0	0		-	0	-	0
83	0	-	0	0		-		-	0
					1				
					1				
	_			_					

Table C-9 Site Geology (Continued)

Appendix D

Chi-Square Contingency Tables

- Table D-1 Chi-Square Contingency Table for Cost vs. Contaminant
- Table D-2 Chi-Square Contingency Table for Schedule vs. Contaminant
- Table D-3 Chi-Square Contingency Table for Cost vs. Technology
- Table D-4 Chi-Square Contingency Table for Schedule vs. Technology
- Table D-5 Chi-Square Contingency Table for Scope Change vs. Technology
- Table D-6 Chi-Square Contingency Table for Cost vs. Reason for Technology Selection
- Table D-7 Chi-Square Contingency Table for Schedule vs. Reason for Technology Selection
- Table D-8 Chi-Square Contingency Table for Scope Change vs. Reason for Technology Selection

		Cost vs Contaminant				
Observed Frequency						
Over Budget On /Under Budget Column Total	Chlorinated Solvents 26.47 73.53	Fuel Hydrocarbons 36.59 63.41 100.00	Metals 20.83 79.17 100.00	Other Contaminants 42.86 57.14 100.00	PCBs 36.36 63.64 100.00	Row Total 163.11 336.89 500.00
Expected Frequency Over Budget On /Under Budget Column Total	Chlorinated Solvents 32.62 67.38 100.00	Fuel Hydrocarbons 32.62 67.38 100.00	Metals 32.62 67.38 (00.00	Other Contaminants 32.62 67.38	PCBs 32.62 67.38 100.00	Row Total 163.11 336.89 500.00
Chi-Square Terms Over Budget On /Under Budget	Chlorinated Solvents 1.1600 0.5616	Fuel Hydrocarbons 0.4815 0.2331	Metals 4.2601 2.0626	Other Contaminants 3.2113 1.5548	PCBs 0.4292 0.2078	
Chi-Square: Alpha: Critical Value:	14.16 0.0010 18.4662 Accept Ho					
Decision:	Accept no					

Table D-1 Chi-Square Contingency Table for Cost vs Contaminant

		Schedule vs Contaminant	ant			
Observed Frequency				2450		
Behind Schedule On / Ahead of Schedule Column Total	Chlorinated Solvents 17.65 82.35 100.00	Fuel Hydrocarbons 26.83 73.17 100.00	Metals 25.00 75.00 100.00	Contaminants 35.71 64.29 (100.00	PCBs 18.18 81.82 100.00	Row Total 123.37 376.63 500.00
Expected Frequency				Other		
Behind Schedule On / Ahead of Schedule Column Total	Chlorinated Solvents 24.67 75.33 100.00	Fuel Hydrocarbons 24.67 75.33 100.00	Metals 24.67 75.33 100.00	Other Contaminants 24.67 75.33 100.00	PCBs 24.67 75.33 100.00	Row Total 123.37 376.63 500.00
Chi-Square Terms				2450		
Behind Schedule On / Ahead of Schedule	Chlorinated Solvents 2.0014 0.6556	Fuel Hydrocarbons 0.1882 0.0616	Metals 0.0043 0.0014	Contaminants 4.9394 1.6180	PCBs 1.7084 0.5596	
Chi-Square:	11.74		11.74			·
Alpha: Critical Value: Decision:	0.01 13.2767 Accept Ho		0.0194 11.7392 Accept Ho			

Table D-2 Chi-Square Contingency Table for Schedule vs Contaminant

			Cost vs Technology	ology					
Observed Frequency								Seil Wester	
Over Budget On / Under Budget Column Total	Air Sparging 0 100 100.00	Biodegradation 20 80 100:00	Composting 100 0 100.00	Land Disposal 20 80 100.00	Other Technologies 30.8 69.2 100.00	Pump and Treat 30.8 69.2 100.00	Soll Cap 33.3 66.7 100.00	Soil Vapor Extraction 16.7 83.3 100.00	Row Total 251.60 548.40 600.00
Expected Frequency	Air Sparding	Biodegradation	Composting	Land Disposal	Other Technologies	Pump and Treat	Soil Cap	Soil Vapor Extraction	Row Total
Over Budget On / Under Budget Column Total	31.45 68.55 100.00	31.45 68.55 100.00	31.45 68.55 100.00	31.45 68.55 100.00	31.45 68.55 100.00	31.45 68.55 100.00	31.45 68.55 100.00	31.45 68.55 100.00	251,80 548.40 800.00
Chi-Square Terms								Soil Vapor	
Over Budget On / Under Budget	Air Sparging 31.4500 14.4289	Biodegradation 4.1686 1.9125	Composting 149.4150 · 68.5500	Land Disposal 4.1686 1.9125	Other Technologies 0.0134 0.0062	Treat 0.0134 0.0062	Soil Cap 0.1088 0.0499	6.9177	
Chi-Square:	286.2956		286.2956						
Alpha: Critical Value: Decision:	0.01 18.4753 Reject Ho		0.0010 24.3213 Reject Ho						

Table D-3 Chi-Square Contingency Table for Cost vs Technology

			Schedule vs Technology	chnology					
		,							
Observed requestry Behind Schedule Ahead / On Schedule	Air Sparging 50.00 50.00	Biodegradation 0 100	Composting 75 25	Land Disposal 10 90	Other Technologies 23.1 76.9	Pump and Treat 15.4 84.6 100.00	Soil Cap 16.7 83.3 100.00	Soil Vapor Extraction 41.7 58.3 100.00	Row Total 221,90 568.10 600,00
Column Total	00.001	COCCO TO							
Behind Schedule Ahead / On Schedule	Air Sparging 28.99 71.01	Biodegradation 28.99 71.01	Composting 28.99 71.01	Land Disposal 28.99 71.01 100.00	Other Technologies 28.99 71.01 100.00	Pump and Treat 28.99 71.01	Soil Cap 28.99 71.01 100.00	Soli Vapor Extraction 28.99 71.01	Row Total 231.90 568.10 800.00
Column Local	876								
Behind Schedule Ahead / On Schedule	Air Sparging 15.2316 6.2176	Biodegradation 28.9875 11.8328	Composting 73.0367 29.8138	Land Disposal 12.4373 5.0769	Other Technologies 1.1958 0.4881	Pump and Treat 6.3690 2.5998	Soil Cap 5.2085 2.1261	Soil Vapor Extraction 5.5751 2.2758	
Chi-Square:	208.47		208.47						
Alpha: Critical Value: Decision:	0.01 18.4753 Reject Ho		0.0160 17.2253 Reject Ho						

Table D-4 Chi-Square Contingency Table for Schedule vs Technology

			Score Change vs Technology	vs Technolo	λĎ				
!		•	عرامه		;				
Observed Frequency					Pare	Pump and		Soil Vapor	-
	Ale Cassaina	Riodeoradation	Composting	Land	Technologies	Treat	Soil Cap	Extraction	Row Total
	Rinkindo IIV	- OV	75	ළ	38.5	46.2	33.3	ይ	338.00
Increased Scope		? 2	, K	2	61.5	53.8	66.7	ß	462.00
Decreased / Unchanged S	5 (3 100.00	100.001	100:00	100.00	100.00	100.00	100.00	100.00	900.00
Expected Frequency					20,00	Dag ami		Soil Vapor	
			Compostino	Land	Orner Technologies	Treat	Soil Cap	Extraction	Row Total
	Air Sparging	Blodegradation	Sunsoding A2 25	42.25	42.25	42.25	42.25	42.25	338.00
Increased Scope		67.24	57.75	57.75	57.75	57.75	57.75	57.75	462.00
Decreased / Unchanged S	S 57.75	5/./5 100.00	100.00	100.00	100.00	100:00	100.00	100.00	800.00
Column 1 otal	Control 1								
Chi-Square Terms								Soit Vanor	
		1000	Compacting	Land	Other Technologies	rump and Treat	Soil Cap	Extraction	
	Air Sparging	Biodegradation 0 1198	25.3861	3.5518	0.3328	0.3693	1.8959	1.4216	
Increased Scope Decreased / Unchanged	ú	0.0877	18.5725	2.5985	0.2435	0.2702	1.3871	1.0400	
Chi-Square:	69.47		69.47						
	0.0		0.0010			•			
Criffical Value:	18.4753		24.3213						
Decision:	Reject Ho		Reject Ho						

Table D-5 Chi-Square Contingency Table for Scope Change vs Technology

	3	ost vs Reason	Cost vs Reason for Technology Selection	election			
Observed Frequency			Regulatory	Minimal Exposure		AFCEE	144
Over Budget On or Under Budget	Schedule 41.2 58.8	Cost 32.4 67.6	Requirements 30.8 69.2	Hazard 27.5 72.5	Effectiveness 27.1 72.9	Guidance 25 75	184.00 416.00 600.00
Column Total	100.00	100.00	100:00	100:00	100.00	acioni l	
Expected Frequency				Minimal Expectito		AFCEE	
	Schedule 30.67	Cost 30.67	Regulatory Requirements 30.67	Minimal Exposure Hazard 30.67	Effectiveness 30.67	Guidance 30.67	Row Total 184,00
Over Budget On or Under Budget Column Total	69.33	69.33	69.33	69.33	69.33	100.00	600,00
Territoria							
Over Budget	Schedule 3.6180 1.6003	Cost 0.0980 0.0433	Regulatory Requirements 0.0006 0.0003	Minimal Exposure Hazard 0.3270 0.1446	Effectiveness 0.4148 0.1835	AFCEE Guidance 1.0471 0.4631	
Chi-Square:	7.94		7.94			·	
Alpha: Critical Value:	15.0863		0.1000 9.2363 Accept Ho				
Decision:	Accept no						

Table D-6 Chi-Square Contingency Table for Cost vs Reason for Technology

	3	hadiile ve Res	Schodule ve Reason for Technology Selection	gy Selection			
	on.	reduie va ive				1.00	
Observed Frequency	dispara	Cost	Regulatory Requirements	Minimal Exposure Hazard	Effectiveness	Guidance	Row Total
Behind Schedule	17.7	26.3	, 8	9.1	22.9 77.1	12.5 87.5	491.50
On Schedule Column Total	100.00	100:00	100:00	100.00	100.00	100:00	600.00
Expected Frequency			100	Minimal Exposure		AFCEE	
	Schedule	Cost	Regulatory Requirements	Hazard	Effectiveness	Guidance 18.08	Row Total 108.50
Behind Schedule	18.08	18.08	18.08 81.92	81.92	81.92	81.92	491.50
On Schedule Column Total	61.92 100.00	100:00	100:00	100.00	100.00	100:00	900.00
Chi-Square Terrns			Regulatory	Minimal Exposure		AFCEE	
	oli ibado	Cost	Requirements	Hazard	Effectiveness	Guidance	
Behind Schedule	0.0081	3.7335	0.2031	4.4627 0.9852	1.2830 0.2832	1.7239 0.3806	
On Schedule	0.0010	0.057					
Chl-Square:	13.93		13.93			•	
	0.01		0.0160				
Alpha. Catical Value:	15.0863		13.9392				
Decision:	Accept Ho		Accept Ho				

Table D-7 Chi-Square Contingency Table for Schedule vs Reason for Technology

	Š	ope Change v	s Reason for Tech	Scope Change vs Reason for Technology Selection			
Observed Frequency increased Scope Dec / No Change Column Total	Schedule 17.7 82.36 100.06	Cost 50 50.01	Regulatory Requirements 37.5 62.50 100.00	Minimal Exposure Hazard 27.3 72.73 100.03	Effectiveness 6.25 93.75 (100.00	AFCEE Guidance 25 75.00 100.00	Row Total 163.75 436.34 600.09
Expected Frequency Increased Scope Dec / No Change Column Total	Schedule 27.30 72.76 100.06	Cost 27.29 72.72 100.01	Regulatory Requirements 27.29 72.71	Minimal Exposure Hazard 27.29 72.73 100.03	Effectiveness 27.29 72.71 (100.00	AFCEE Guidance 27.29 72.71 100.00	Row Total 163,75 436.34 600.09
Chi-Square Terms Increased Scope	Schedule 3.3779	Cost 18.9011 7.0932	Regulatory Requirements 3.8221 1.4343	Minimal Exposure Hazard 0.0000	Effectiveness 16.2190 6.0867	AFCEE Guidance 0.1918 0.0720	
Dec / No Change Chi-Square:	58.47		58.47				
Alpha: Critical Value: Decision:	0.01 15.0863 Reject Ho		0.0010 20.5147 Reject Ho				

Table D-8 Chi-Square Contingency Table for Scope Change vs Reason for Technology

Bibliography

Air Force Center For Environmental Excellence (AFCEE). (June 1994). <u>Use of Risk-Based Standards for Cleanup of Petroleum Contaminated Soil</u>. AFCEE, Armstrong Laboratory, Brooks Air Force Base, San Antonio, TX, and the Air Force Institute of Technology, Wright-Patterson Air Force Base, Dayton, OH.

Allen, Scot Tolbert, (December, 1997). Remediation Technologies for Environmental Projects in the United States Military: Part I.

Blackburn, J. W.; Robbins, W. K.; Prince, R. C.; Harner, E. J.; Clark, J. R.; Atlas, R. M.; and Wilkinson, J. B. (March 1993). "Environmental Comparisons in Petroleum Site Remediation," <u>American Chemical Symposium on Bioremediation and Bioprocessing Presented at the 205th National Meeting of the American Chemical Society (ACS), 28 March – 2 April 1993. ACS, p. 254-259.</u>

Blalock, Hubert M. Jr. (1979) Social Statistics. McGraw Hill, Inc., New York, NY.

The Construction Industry Institute (CII). (October 1995). "Environmental Remediation," Published by CII, Austin, TX, Research Summary 48-1.

Department of Defense (DOD) Environmental Technology Transfer Committee, Federal Remediation Technologies Roundtable. (1994). <u>Remediation Technologies Screening Matrix and Reference Guide</u>. National Technical Information Service, Washington, DC.

Department of the Navy (DON) (1996). <u>Department of the Navy Environmental Restoration For Fiscal Years 1997-2001</u>.

Kenkeremath, Nandan. (September 1996). "Restoring Reason to Regulation: Applying Scientific Assessment and Cost-Benefit Analysis to Environmental Law," American Industrial Hygiene Association Journal, Vol. 57 (9), p. 791-793.

LaGrego, M. D.; Buckingham, P. L.; and Evans, J. C. (1994). <u>Hazardous Waste Management</u>. Environmental Resources Management Group (ERM) and McGraw Hill, Inc., New York, NY.

Middleton, Michael R. (1995). <u>Data Analysis Using Microsoft Excel 5.0</u>. Duxbury Press. Wadsworth Publishing Company. Belmont, CA.

Scalf, M. R. (December 1992). "EPA's Superfund Technical Support Project," *Journal of Hazardous Materials*, Vol. 32 (2-3), p. 313-319.

Spain, Jim C. (August 1992). "Biotech Research: A Proactive Approach," <u>The Military Engineer</u>, Vol. 92 (3), p. 46-48.

U. S. Environmental Protection Agency (EPA). Technology Innovation Office. (1997). Hazardous Waste Cleanup Information Web Site (http://clu-in.com). Internet.

United States of America Federal Budget Fiscal Year 1998.

VITA

Joseph Aloysius Campbell was born in Portsmouth, Virginia on 17 February 1964, the son of Captain and Mrs. Donald Berlin Campbell, CEC, USN. After completing his work at Gaithersburg High School, Gaithersburg, Maryland, in 1982, he enlisted in the U.S. Navy and was ordered to the Naval Academy Preparatory School in Newport, Rhode Island. Following preparatory school, he attended the U.S. Naval Academy in Annapolis, Maryland. He received the degree of Bachelor of Science in Mechanical Engineering in May, 1987. During the following years, he served as a Naval Officer in engineering billets on the USS Dewey (DDG-45), as Assistant Officer in Charge of Construction at Charleston Naval Shipyard, Charleston, South Carolina, as Planning and Programming Officer at the Public Works Center at Naval Air Station, Pensacola, Florida, and as Company Commander, Detail Officer in Charge, and Training Officer of U.S. Naval Mobile Construction Battalion ONE. He is a registered Professional Engineer in the State of Alabama. In May, 1997, he entered The Graduate School at The University of Texas. He is married to the former Susanna Dawson Haralson of Scottsboro, Alabama. They have two children, William and Kathryn.

Permanent Address: 409 College Avenue

Scottsboro, Alabama 35768

This thesis was typed by the author.